

WORKSHOP AGENDA

Planning Commission

March 11, 2025 @ 5:30 PM

For the March 25, 2025 Regular Meeting @ 6:00 PM

- Call meeting to order.
- Determine quorum.

ORDER OF BUSINESS

1. Approve Minutes: February 25, 2025 Regular Meeting and March 11, 2025 Workshop.
2. Public Comment Period.

NEW BUSINESS

3. Recommendation to the Board of Mayor and Aldermen: Rezoning of Property - Requested by Equitable Property Company, LLC - 76.55 Acres. Property located on and near Waldron and Blair Roads (Tax Map 32, Parcels 3.04 and 3.05 and Tax Map 29, Parcels 41.01 and 41.02). Current Zoning District: R-1 (Low Density Residential) Zoning District; Proposed Zoning District: PDR R-3 (Planned Density Residential) Zoning District with a Base Zone of R-3 (High Density Residential). Property owned by the Industrial Development Board of the City of La Vergne.
4. Recommendation to the Board of Mayor and Aldermen for Subdivision Acceptance - Portico Place, Section 2, Phase 2 and Resubdivision of Common Areas A & B of Section 2, Phase 1. Requested by SEC, Inc. Property located off Blair Road (Tax Map 29, Parcel 20.04). PDR (Planned Density Residential) Zoning District.
5. Discussion - Property on Corner of Old Nashville Highway and Woody Thomas Drive.
6. Discussion - New Zoning Ordinance.
7. Bonds/Letters of Credit Update.

ADJOURN



Item #: 3. **Item Title: Recommendation to the Board of Mayor and Aldermen: Rezoning of Property - Requested by Equitable Property Company, LLC - 76.55 Acres. Property located on and near Waldron and Blair Roads (Tax Map 32, Parcels 3.04 and 3.05 and Tax Map 29, Parcels 41.01 and 41.02). Current Zoning District: R-1 (Low Density Residential) Zoning District; Proposed Zoning District: PDR R-3 (Planned Density Residential) Zoning District with a Base Zone of R-3 (High Density Residential). Property owned by the Industrial Development Board of the City of La Vergne.**

Reviewed By:
Bo Logan, City Planner
Gary Lide, City Engineer

Summary:

Equitable Property Company is requesting approval of a concept plan and rezoning for Rock Springs Mixed Use, a mixed use PDR to consist of 76.55 acres. The accompanying rezoning request would change the 76.55 acres from R-1 to R-3 PDR, Planned Density Residential Zoning District (High Density Residential).

The property is located along the west side of Waldron Road and south of Blair Road in the southern part of LaVergne. Furthermore, this site lies east of The Ridge subdivision. Arbor Ridge, under construction, is across Waldron Rd. A future connection point is shown to Blair Road West when it is completed.

Directly across the street to the east (Arbor Ridge) of this site is zoned R-1 PDR. All the property to the south of this site is zoned R-1. Nextdoor to this site The Ridge is zoned R-1 and later phases R-2.

The purpose of the plan is to develop the property for construction of 614 dwelling units to include single-family homes and multi-family units.

This proposal also calls for approximately 208,000 square feet of space to be used as commercial and office uses including property for restaurant and/or retail purposes. The developers will also designate approximately 2 acres to be set aside for a future fire hall. The Concept Plan also calls for amenities including a pool, club house, walking trail and a playground among others.

The development would extend to the south near Rock Springs Elementary School, although it will stop short of Lake Road. It is conceivable that one day in the future children living in Rock Springs could walk to the school.

Staff Comments / Technical Items:

Planning (Bo Logan - blogan@lavernetn.gov; and Jake Blair - jblair@lavernetn.gov)

1. The Design Book needs to clearly state the exact percentage of brick and stone that will be applied to the front of every home and/or dwelling;
2. For heights above 35 feet this development must make application to BOZA for a hearing;
3. Upward of 90% of the total number of dwelling units are multi-family. The zoning ordinance only allows a maximum of 30% unless the development is a private community with a Homeowners Association with a property management policy. Please provide clear verbiage in the Design Book that confirms this;

4. The Design Book indicates a possible 50,000 SF grocery store. But Section 5.052.6 only allows a maximum commercial size of 3,000 SF per establishment unless sufficient design considerations are presented to the Planning Commission by the developer for an exception to this rule;
5. Plan must show min. 20% open space for entire development;
6. Transitional Screening 2 per Section 3.130 is required around the entire PDR wherever the PDR abuts residential zoning;
7. The Zoning Ordinance requires that a copy of the bylaws and restrictive covenants be provided to staff;
8. Zoning Ordinance does not allow 6 townhomes with same setback as shown in the Design Book - the zoning only allows five contiguous townhomes with the same setback.
9. All take-out and drive-thru windows and facilities require permission from the Planning Commission during this stage - requests should be made and shown in the Design Book.

Engineering (Gary Lide - glide@laveragnetn.gov)

1. (Zoning Ordinance section 5.052.6, C) The site is requesting a rezoning from a base zone of R1 to 'PDR with an R3 base zone'. For information:
 - a. Maximum number of dwelling units on this site based on R1 zoning = $2.904 \text{ DU/acre} \times 76.55 \text{ acres} = 222 \text{ DUs}$.
 - b. The maximum number based on R3 zoning is $14.52 \text{ DU/acre} \times 76.55 \text{ acres} = 1,111 \text{ DUs}$.
 - c. The number shown on the plans = 614 DUs.
2. (Zoning Ordinance section 5.052.6, D 4) Page 4 of the Design Booklet states that buildings will be up to four stories. Zoning Ordinance allows a maximum of three. THERE IS NO EXCEPTION ALLOWED BY THE PLANNING COMMISSION FOR THIS.
3. (Zoning Ordinance section 5.052.6, I 2) Provide square foot estimate for all residential uses to determine whether commercial is $\leq 50\%$. Unless the average dwelling unit is 960 SF, this PDR will NOT meet the requirements of Zoning Ordinance section I 2 (page 91). Please provide a table of dwelling unit types with minimum floor areas in the Design Booklet to confirm that the average size of all dwelling units will be 960 SF or more. Building permits will not be issued for any dwelling units smaller than the minimum size shown on the provided table. THERE IS NO EXCEPTION ALLOWED BY THE PLANNING COMMISSION FOR THIS.
4. Sewer capacity planning for the two sewers serving this area was based on existing zoning and projected uses. This present submittal shows 614 dwelling units and 288,725 SF nonresidential which are about 150% of those projections. Significant public infrastructure costs above what is presently planned will likely be required by this increase. These are very roughly estimated at a minimum of \$9 million to a maximum of over \$11 million.
5. (Zoning Ordinance section 5.052.6, I 3) Page 6 of the Design Booklet shows a 50,000 SF grocery store for consideration of the Planning Commission for an exception to the maximum commercial size of 3,000 SF. No other exceptions are requested. This means that, if this PDR is approved as is, then a building permit cannot be issued for any commercial use (other than the grocery store) which is over 3,000 SF without going through the complete rezoning process.
6. Page 23 of the Design Booklet calls out for 'Food Service (take-out and drive-thru)' to be a permitted use. This requires an Exception to Zoning Ordinance Section (Zoning Ordinance section 5.052.6, I 4). This request for an exception must be clearly called out. It is not recommended for the Planning Commission to consider any exception to be granted based on wording within the Design Booklet unless that exception is clearly and specifically called out in the submittal.
7. (Zoning Ordinance section 5.052.6, G 8) 97% of the total number of dwelling units are attached, multi-family, condominiums, or townhomes. A maximum of 30% is allowed "unless the development is a private community with a Homeowners Association with a Property Management Policy". Please provide clear verbiage in the Design Booklet that confirms that this is such a development, that it cannot be anything other than such a development, and provides details of the property management policy.
8. On page 32 of the Design Booklet, it states that "the property does not lie within any floodplain areas and is fully within Zone "X" as shown on panel 47149C0105J, date 09 May 2023. Staff concurs with the statement that this is what is shown on that map. However, the Flood Insurance Study for that reach (Sheet 14P) states that the limit of the detailed study for East Branch Hurricane Creek stops immediately north of this property and the reach of the creek through the subject property is therefore unstudied. Please provide calculations showing the 100-year flood elevations through the site and map those elevations on the Site Topography (page 32 of the Design Booklet).
9. Provide all hydraulic calculations required by the La Vergne Stormwater Management Ordinance Section 14-603 (5) (c) (i) which is specific to Concept Plans.
10. Provide a traffic study for this development.
11. Stream buffers in La Vergne are 60 feet from top of bank in both directions. Therefore, the total buffer is the width of the stream + 120 feet. Show the stream buffers at the correct width.
12. On page 7 of the Design Booklet, state what the surfacing of the walking trails will be.
13. On pages 24 and 25 of the Design Booklet, provide a maximum percentage of Natural Wood Accents
14. On pages 24 and 25 of the Design Booklet, provide a maximum percentage of Cementitious Panels + Lap Plank Siding

15. On page 8 of the Design Booklet, please add a note stating that a 35-foot transitional buffer meeting all requirements of a Transitional Screening 2 per the Zoning Ordinance Section 3.130 will be required around the complete perimeter of the PDR wherever the PDR abuts a residential zoning.
16. On page 8 of the Design Booklet, please add a note stating that a 50-foot transitional buffer meeting all requirements of a Transitional Screening 3 per the Zoning Ordinance Section 3.130 will be required around the complete perimeter of the PDR wherever the PDR abuts a nonresidential zoning.
17. Transition Buffer Requirements where the PDR abuts another PDR should be discussed with the City Planner.
18. While page 23 of the Design Booklet states that the HOA will be subject to restrictive covenants, Zoning Ordinance Section 5.052.6, G 1 requires that a copy of the bylaws or restrictive covenants be provided.
19. In two locations on page 5 of the Design Booklet, six townhomes are shown graphically as having the same setback. Zoning Ordinance Section 5.052.6, G 5 only allows five contiguous townhomes with the same setback.
20. Page 33 of the Design Booklet (Site Survey) is intended to show the required information regarding surrounding property owners, but the surrounding property owner information is not readable. Provide a copy of that page where this required information is readable. This is required by Section 3-101.2.1 of the Subdivision Regulations which is required by Zoning Ordinance Section 5.052.6, G 1
21. 5' contours must be provided on page 32 of the Design Booklet as required by Section 3-101.2.4 of the Subdivision Regulations which is required by Zoning Ordinance Section 5.052.6, G 1

Utilities (Scott Tatalovich - statalovich@lavergn.net)

Comments included in Engineering comments above.

Codes (Joe White - jwhite@lavergn.net)

No comments.

Fire (Curtis Brinkley - cbrinkley@lavergn.net)


No comments.

Police


No comments.

***Note:** The above technical items may not be the only corrections and/or issues needing to be resolved to get approval from the planning commission. New items can be brought up at the workshop and staff can add items at any time that might have been overlooked. It is the applicant's responsibility to make sure that all technical items are addressed and that no new issues exist before the planning commission meeting. Addressing all technical items does not constitute approval. It is the planning commission's decision whether an item passes or fails. Revised plans are due to staff by the following Monday at close of business unless other arrangements are made and documented.


SOUTH WALDRON ROAD MIXED USE DEVELOPMENT



SOUTH WALDRON ROAD MIXED USE DEVELOPMENT



SOUTH WALDRON ROAD MIXED USE DEVELOPMENT









SOUTH WALDRON ROAD MIXED USE DEVELOPMENT

CITY OF LA VERGNE, TN

A REQUEST FOR REZONING FROM LOW DENSITY RESIDENTIAL (R-1) TO PLANNED DENSITY RESIDENTIAL (PDR)



TABLE OF CONTENTS

PROJECT VISION 3

DEVELOPMENT VISION 4

OPEN SPACE 7

RESIDENTIAL BUFFER ZONE..... 8

BUILDING TYPOLOGY - COMMERCIAL / MIXED USE 8

BUILDING TYPOLOGY - AMENITY AREAS 9

BUILDING TYPOLOGY - RESIDENTIAL 10

BUILDING TYPOLOGY - MEDICAL OFFICE AND FIRE HALL..... 11

PEDESTRIAN 13

VEHICULAR STREET ACCESS 14

ECONOMIC IMPACT 15

DEVELOPMENT INVESTMENT 16

POTENTIAL MERCHANDISING PLAN..... 17

R.O.W DEDICATION 22

DEVELOPMENT STANDARDS 23

ARCHITECTURAL STANDARDS..... 23

ARCHITECTURAL STANDARDS..... 24

ARCHITECTURAL STANDARDS..... 25

ARCHITECTURAL STANDARDS..... 26

ARCHITECTURAL STANDARDS..... 27

SUBDIVISION DEVELOPMENT AND AREA DEMOGRAPHICS..... 28

EXISTING SUBDIVISION..... 29

EXISTING ZONING 30

SITE UTILITIES..... 31

SITE TOPOGRAPHY 32

SITE SURVEY 33

PLANT PALETTE..... 34

VISION IMAGERY 35

PROJECT TEAM

EQUITABLE PROPERTY COMPANY
3201 Trevor St
Suite 200
Nashville, TN 37209
land@equitableTN.com
615.948.6807

LAND DELEOT
DEVELOPER

SCOTT DISMUKES
PLANNER +
LANDSCAPE ARCHITECT

PAUL BASS
PLANNING +
ARCHITECTURE

firma Studio
507 Hagan Street
Nashville, TN 37203
scott@firmastudio.com
610.316.2813

CONSTORTIUM
1104 W Main Street
Franklin, TN 37064
PaulB@consorti4.com
615.570.2780

FULMER LUCAS
2002 Richard Jones Road
Suite B200
Nashville, TN 37215
jay@fulmerlucas.com
615.345.3771

JAY FULMER
CIVIL ENGINEER



PROJECT VISION

The proposed South Waldron Mixed-Use Development encompasses approximately 76.55 acres and is designed to establish a vibrant, integrated community that harmonizes residential, commercial, and recreational elements. The master-planned development will feature a balanced mix of housing, retail, and open spaces, fostering pedestrian connectivity and long-term growth potential. This project is positioned to become a key destination for living, working, shopping, and leisure, attracting both local and national interest.

Rezoning Request & Site Plan

The subject property is strategically located along Waldron Road, with direct integration into the planned Blair Road Extension. To accommodate the proposed development, we seek rezoning from Low-Density Residential (R-1) to Planned Density Residential (PDR) to support a diverse range of residential and commercial uses.

Approximately 4 acres will be allocated for road infrastructure improvements, ensuring enhanced connectivity with the city's broader transportation network.

Residential Component

- The development shall include a mix of single family, multi-family, and townhomes.
- Single-Family Homes – 16 lots featuring masonry facades and two-car garages to maintain a high-quality streetscape.
 - Townhomes – 36 units with fifty percent masonry exteriors and options for front-entry or alley-loaded garages, ensuring architectural consistency.

- Multifamily Residences – The residential and pedestrian-friendly section will feature 320 units within three- to four-story buildings, offering a mix of on-street, surface, garage, and carport parking for resident convenience. Additionally, the commercial and mixed-use portion of the development will include 242 additional units, integrating residential living with retail and office spaces for a dynamic, walkable community.

All residential units will feature foundation landscaping and sod in the primary and secondary front yards, while strategically placed street lighting will enhance both aesthetics and public safety.

Town Center & Retail Spaces

At the heart of the development, the Town Center will serve as a pedestrian-friendly hub, integrating retail, dining, and community gathering spaces.

- Retail – 120,200 square feet of scale retail space, strategically positioned on out parcels and along the central median to maximize visibility and accessibility.
 - Grocery Store – A ±50,000 square-foot grocery store to serve both residents and the surrounding community.
 - Sidewalk & Trail Connectivity – Pedestrian access will be prioritized through an interconnected network of walkways and trails, seamlessly linking retail, dining, and residential areas.
 - Vibrant Streetscape – Designed to promote foot traffic, featuring dining terraces and retail frontages, fostering an active and engaging environment for both residents and visitors.
- Amenities & Open Spaces

Approximately 43% of the total site is dedicated to open space, ensuring a high quality of life for residents and visitors. These areas will include:

- Pocket Parks & Village Greens – Strategically distributed throughout the development to provide accessible green spaces.
- Amenity Center – A central clubhouse with a pool, sun deck, playgrounds, and fire pits, fostering a sense of community.
- Trail System – Designed to complement natural tributaries, providing scenic walking and biking opportunities while ensuring connectivity across the development.
- Creek - Restoration of the creek creating natural buffer areas throughout the site.

Community Oversight & Maintenance

A Residential and Commercial Homeowners Association (HOA) will be established to oversee:

- Common area maintenance
- Primary entrance aesthetics and upkeep
- Signage regulations to maintain cohesive branding and architectural consistency

This rezoning request is critical to achieving the envisioned mixed-use development, which will increase housing diversity, enhance economic vitality, and strengthen the community's overall infrastructure.




DEVELOPMENT VISION

South Waldron Site represents versatile commercial properties designed to serve a wide range of business needs and community services providing convenience and connectivity. With thoughtfully planned infrastructure, ample parking, and enhanced landscaping, the site is ideal for businesses seeking a dynamic location with easy access and sustainable design with the goal to provide a well-integrated and sustainable environment for businesses to thrive.

- Diverse Business Potential: Approved uses include retail, food and beverage, professional services, animal care, daycare, medical services, and more.
- Strategic Accessibility: Located along Waldron and Blair Roads, featuring pedestrian and vehicular connections for easy access.
- Sustainable & Aesthetic Design: Includes foundation planting, architectural details, and landscaping that enhance property value and appeal.
- Functional & Safe Spaces: Compliance with safety standards, solid waste management, and the latest in stormwater systems.
- Modern Signage and Lighting: Exterior illumination aligned with La Vergne’s zoning standards and lighting ordinance.
- Building Design: Up to 4 stories with architectural enhancements such as base differentiation and main entry articulation.
- Landscaping & Screening: Landscape screening for parking, perimeter edge screening, and foundation planting around buildings.
- Parking & Accessibility: Setbacks of 10 feet from rights-of-way, shared parking options, and connectivity with nearby roads.
- Waste & Utilities Management: Private solid waste collection, screened equipment, and shared drainage and parking maintenance by an owners’ association where applicable.
- Community Safety: Donation of land for a new fire department, an essential resource for La Vergne. The new fire station will serve the growing community’s needs. Located within close proximity to both residential and commercial zones, this new facility will bolster emergency response capabilities, benefiting residents, businesses, and surrounding neighborhoods alike.

OVERALL SITE PLAN





- *NOTES:**
1. PENDING MARKET DEMAND THE USES ABOVE RETAIL SHALL ALLOW THE FLEXIBILITY OF RESIDENTIAL OR OFFICE ABOVE RETAIL
 2. **MAINTENANCE:** THE PROPOSED MEANS OF ASSURING THE CONTINUED MAINTENANCE OF THE COMMON OPEN SPACES AND OTHER COMMON ELEMENTS SHALL BE BY THE COMMERCIAL AND RESIDENTIAL HOMEOWNERS ASSOCIATIONS THAT WILL BE CREATED FOR THE DEVELOPMENT.
 3. **PARKING:** ALL PARKING REQUIREMENTS WILL BE EVALUATED AT THE SITE PLAN STAGE FOR EACH SECTION OF THIS DEVELOPMENT. A SHARED PARKING STUDY SHALL BE PROVIDED FOR THE MIXED USE TOWN CENTER.
 4. **SIGNAGE:** ALL PROPOSED SIGNS SHALL CONFORM TO THE CITY OF LA VERGNE SIGN ORDINANCE, OR A SPECIAL REQUEST BY BOZ FOR ALTERNATIVE SIGNAGE OPTIONS.
 5. THE DEVELOPER REQUESTS THAT THE BUILDING AND PARKING ARRANGEMENTS SHALL HAVE FLEXIBILITY AS MARKET DEMANDS AS IT RELATES TO THE FUTURE LOCATIONS AND CONFIGURATIONS AS LONG AS THE OVERALL PROPOSED BUILDING SQUARE FOOTAGE/UNIT IS NOT EXCEEDED.

SITE DATA / KEY (FIRMA CONCEPT PLAN)	
	FIRE STATION (2.0 AC / 6,000 SF FOOTPRINT): 3 BAYS
	COMMERCIAL/RETAIL/OFFICE (208,006 SF): 5.9 /1,000 PARKING (SHARED)
	OFFICE ABOVE RETAIL (30,720 SF): 3/1,000 PARKING (SHARED)
	GROCERY (50,000 SF): 5/1,000 PARKING
	SINGLE FAMILY (16 LOTS)
	TOWN HOMES (36 DWELLING UNITS): 3 / UNIT PARKING
APARTMENTS : (MIN. REQ. FOR GATED APARTMENT COMPLEXES PARKING)	
	GATED MIXED USE MULTIFAMILY: 320 UNITS
	MULTIFAMILY ABOVE RETAIL: 242 UNITS
	RESIDENTIAL AMENITY/CLUBHOUSE
	TRAIL (1.75 MILES)
	BUFFER
	DETENTION (100,000 SF)

SITE DATA

SITE ACREAGE: +/- 76.55 AC
EXISTING ZONING: R-1
PROPOSED ZONING: PDR (PLANNED DENSITY RESIDENTIAL)
TOTAL RESIDENTIAL DWELLING UNITS:
SINGLE FAMILY: 16 LOTS
GATED TOWNHOMES: 36 UNITS
GATED MIXED USE MULTIFAMILY: 320
MULTIFAMILY ABOVE RETAIL: 242
TOTAL COMMERCIAL/RETAIL/OFFICE SF: 208,006 SF

ALLOWED USES: Single Family Residential, Residential Multifamily, Residential Senior Housing, Residential Townhomes, Convenience Retail Sales and Services, Consumer Repair Services, Financial, Insurance, Real Estate and Consulting Services, Food and Beverage Services, Food Service (take out and drive-thru), Animal Care & Veterinarian (provided no outside housing of animals), General Business Services, General Personal Services, General Retail Trade, Medical Services, Professional Services (not otherwise listed), Religious Facilities, Daycare, Grocery Stores, Gasoline Station (including beer and tobacco sales), Beauty Parlor, Barbershops, Hardware Store, Drug Store & Pharmacy, Liquor Store, Hotel, and Professional Office

SETBACKS:
Waldron Road Setbacks: Minimum 20'
Blair Road Setbacks: Minimum 20'
Minimum Building Separation: 10'

MAXIMUM BUILDING HEIGHT: 4 Stories

BUFFER INFO

TRANSITIONAL SCREENING SHALL CONSIST OF AN UNBROKEN STRIP OF OPEN SPACE A MINIMUM OF 25 FEET AND PLANTED WITH:


ONE LARGE EVERGREEN TREE WITH AN ULTIMATE HEIGHT OF 40 FEET OR GREATER FOR EVERY 10 LINEAR FEET, PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20 TO 40 FEET FOR EVERY 5 LINEAR FEET, OR WITH THE APPROVAL OF THE CODES ENFORCER ONE LARGE DECIDUOUS TREE WITH AN ULTIMATE HEIGHT OF 50 FEET OR GREATER FOR EVERY 15 LINEAR FEET PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20-40 FEET FOR EVERY 5 LINEAR FEET

TRANSITIONAL SCREENING SHALL CONSIST OF AN UNBROKEN STRIP OF OPEN SPACE A MINIMUM OF 35 FEET AND PLANTED WITH:

ONE LARGE EVERGREEN TREE WITH AN ULTIMATE HEIGHT OF 40 FEET OR GREATER FOR EVERY 10 LINEAR FEET, PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20 TO 40 FEET FOR EVERY 5 LINEAR FEET, PLUS ONE LARGE DECIDUOUS TREE WITH AN ULTIMATE HEIGHT OF 50 FEET OR GREATER FOR EVERY 30 LINEAR FEET, OR WITH THE APPROVAL OF THE CODES ENFORCER ONE LARGE DECIDUOUS TREE WITH AN ULTIMATE HEIGHT OF 50 FEET OR GREATER FOR EVERY 15 LINEAR FEET, PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20-40 FEET FOR EVERY 5 LINEAR FEET, PLUS ONE SMALL DECIDUOUS TREE WITH AN ULTIMATE HEIGHT OF 20 FEET FOR EVERY 12 LINEAR FEET

NOTE: EXISTING VEGETATION SHALL BE COUNTED TOWARDS FULFILLING THESE REQUIREMENTS.

ENLARGED SITE PLAN





ENLARGED SITE PLAN

- *NOTES:**
1. PENDING MARKET DEMAND THE USES ABOVE RETAIL SHALL ALLOW THE FLEXIBILITY OF RESIDENTIAL OR OFFICE ABOVE RETAIL
 2. **MAINTENANCE:** THE PROPOSED MEANS OF ASSURING THE CONTINUED MAINTENANCE OF THE COMMON OPEN SPACES AND OTHER COMMON ELEMENTS SHALL BE BY THE COMMERCIAL AND RESIDENTIAL HOMEOWNERS ASSOCIATIONS THAT WILL BE CREATED FOR THE DEVELOPMENT.
 3. **PARKING:** ALL PARKING REQUIREMENTS WILL BE EVALUATED AT THE SITE PLAN STAGE FOR EACH SECTION OF THIS DEVELOPMENT. A SHARED PARKING STUDY SHALL BE PROVIDED FOR THE MIXED USE TOWN CENTER.
 4. **SIGNAGE:** ALL PROPOSED SIGNS SHALL CONFORM TO THE CITY OF LA VERGNE SIGN ORDINANCE, OR A SPECIAL REQUEST BY BOZ FOR ALTERNATIVE SIGNAGE OPTIONS.
 5. THE DEVELOPER REQUESTS THAT THE BUILDING AND PARKING ARRANGEMENTS SHALL HAVE FLEXIBILITY AS MARKET DEMANDS AS IT RELATES TO THE FUTURE LOCATIONS AND CONFIGURATIONS AS LONG AS THE OVERALL PROPOSED BUILDING SQUARE FOOTAGE/UNIT IS NOT EXCEEDED.

SITE DATA / KEY (FIRMA CONCEPT PLAN)	
	FIRE STATION (2.0 AC / 6,000 SF FOOTPRINT): 3 BAYS
	COMMERCIAL/RETAIL/OFFICE (208,006 SF): 5.9 /1,000 PARKING (SHARED)
	OFFICE ABOVE RETAIL (30,720 SF): 3/1,000 PARKING (SHARED)
	GROCERY (50,000 SF): 5/1,000 PARKING
	SINGLE FAMILY (16 LOTS)
	TOWN HOMES (36 DWELLING UNITS): 3 / UNIT PARKING
APARTMENTS : (MIN. REQ. FOR GATED APARTMENT COMPLEXES PARKING)	
	GATED MIXED USE MULTIFAMILY: 320 UNITS
	MULTIFAMILY ABOVE RETAIL: 242 UNITS
	RESIDENTIAL AMENITY/CLUBHOUSE
	TRAIL (1.75 MILES)
	BUFFER
	DETENTION (100,000 SF)

SITE DATA

SITE ACREAGE: +/- 76.55 AC
EXISTING ZONING: R-1
PROPOSED ZONING: PDR (PLANNED DENSITY RESIDENTIAL)
TOTAL RESIDENTIAL DWELLING UNITS:
SINGLE FAMILY: 16 LOTS
GATED TOWNHOMES: 36 UNITS
GATED MIXED USE MULTIFAMILY: 320
MULTIFAMILY ABOVE RETAIL: 242
TOTAL COMMERCIAL/RETAIL/OFFICE SF: 208,006 SF

ALLOWED USES: Single Family Residential, Residential Multifamily, Residential Senior Housing, Residential Townhomes, Convenience Retail Sales and Services, Consumer Repair Services, Financial, Insurance, Real Estate and Consulting Services, Food and Beverage Services, Food Service (take out and drive-thru), Animal Care & Veterinarian (provided no outside housing of animals), General Business Services, General Personal Services, General Retail Trade, Medical Services, Professional Services (not otherwise listed), Religious Facilities, Daycare, Grocery Stores, Gasoline Station (including beer and tobacco sales), Beauty Parlor, Barbershops, Hardware Store, Drug Store & Pharmacy, Liquor Store, Hotel, and Professional Office

SETBACKS:
Waldron Road Setbacks: Minimum 20'
Blair Road Setbacks: Minimum 20'
Minimum Building Separation: 10'
MAXIMUM BUILDING HEIGHT: 4 Stories

BUFFER INFO

TRANSITIONAL SCREENING SHALL CONSIST OF AN UNBROKEN STRIP OF OPEN SPACE A MINIMUM OF 25 FEET AND PLANTED WITH:
ONE LARGE EVERGREEN TREE WITH AN ULTIMATE HEIGHT OF 40 FEET OR GREATER FOR EVERY 10 LINEAR FEET, PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20 TO 40 FEET FOR EVERY 5 LINEAR FEET, OR WITH THE APPROVAL OF THE CODES ENFORCER ONE LARGE DECIDUOUS TREE WITH AN ULTIMATE HEIGHT OF 50 FEET OR GREATER FOR EVERY 15 LINEAR FEET PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20-40 FEET FOR EVERY 5 LINEAR FEET

TRANSITIONAL SCREENING SHALL CONSIST OF AN UNBROKEN STRIP OF OPEN SPACE A MINIMUM OF 35 FEET AND PLANTED WITH:
ONE LARGE EVERGREEN TREE WITH AN ULTIMATE HEIGHT OF 40 FEET OR GREATER FOR EVERY 10 LINEAR FEET, PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20 TO 40 FEET FOR EVERY 5 LINEAR FEET, PLUS ONE LARGE DECIDUOUS TREE WITH AN ULTIMATE HEIGHT OF 50 FEET OR GREATER FOR EVERY 15 LINEAR FEET, PLUS ONE MEDIUM EVERGREEN WITH AN ULTIMATE HEIGHT OF 20-40 FEET FOR EVERY 5 LINEAR FEET, PLUS ONE SMALL DECIDUOUS TREE WITH AN ULTIMATE HEIGHT OF 20 FEET FOR EVERY 12 LINEAR FEET

NOTE: EXISTING VEGETATION SHALL BE COUNTED TOWARDS FULFILLING THESE REQUIREMENTS.

OPEN SPACE

The South Waldron Mixed Use Site will transform over 43% of its area into thoughtfully designed open space, fostering a welcoming environment for residents and visitors alike. This extensive open space will include a mix of pocket parks, communal green areas, village greens, and natural buffers around existing tributaries. Recreational trails will wind through these green spaces, connecting the community with preserved natural stream buffers and enhancing accessibility to outdoor areas.

Central to the development, the Amenity Center will serve as a community hub, providing a variety of recreational and social amenities. Residents will enjoy a community clubhouse and cabana, a large pool with a sun deck, playgrounds, outdoor fire pits, and convenient access to a comprehensive walking trail network that spans the community. This center will offer ample outdoor seating areas, providing spaces for relaxation and community gatherings, as well as a dedicated playground for children.

In the heart of the mixed-use town center, a pedestrian-friendly network of sidewalks and trails will link the central village green with other community features. Retail jewel boxes, positioned along a central median, will create a dynamic retail experience, while pedestrian zones and robust streetscapes dotted with retail outlets and dining terraces will enrich the community’s social scene. This interconnected design will encourage foot traffic, promoting a vibrant, accessible town center where residents can shop, dine, and enjoy outdoor areas in a cohesive, lively environment.



OPEN SPACE EXHIBIT



RESIDENTIAL BUFFER ZONE

The South Waldron Mixed Use Site plans include the integration of buffers for residential, commercial, and recreational spaces, promoting walkability, reducing commute times, and fostering community engagement. A critical component to ensure seamless transition between different land uses while minimizing potential conflicts.



Buffer zone will serve multiple functions:

- Mitigating Land Use Conflicts: Reduces noise, visual, and operational disruptions between residential, commercial, and industrial areas.
- Enhancing Aesthetic Appeal: Provides green spaces, tree lines, and landscape features that contribute to the overall ambiance of the development.
- Environmental Protection: Manages stormwater, reduces heat islands, and preserves natural habitats.
- Improving Community Livability: Creates a pleasant environment for pedestrians and residents by integrating parks, trails, and open spaces.

Implementation Strategies

- Master Planning Integration: Incorporating buffers early in the site design ensures cohesive land use transitions.
- Zoning and Density Adjustments: Using buffer zones to balance development intensity while meeting regulatory requirements.
- Community Engagement: Gathering input from stakeholders to align buffer features with community expectations.
- Sustainability Initiatives: Implementing green infrastructure (rain gardens, bioswales) to enhance ecological benefits.

Buffer zones are essential components mixed-use developments, providing functional, environmental, and aesthetic benefits. Proper planning and implementation of buffers will contribute to the long-term success and desirability of the development by fostering a balanced and harmonious environment.



RESIDENTIAL BUFFER ZONE EXHIBIT

BUILDING TYPOLOGY

COMMERCIAL / MIXED USE DISTRICT



BUILDING TYPOLOGY

AMENITY AREAS VISION IMAGERY



BUILDING TYPOLOGY

RESIDENTIAL VISION IMAGERY



BUILDING TYPOLOGY

MEDICAL OFFICE AND FIRE HALL VISION IMAGERY




PEDESTRIAN-FOCUSED VISION

The master plan for La Vergne places a strong emphasis on pedestrian sidewalks and access to a network of trails, creating a community where walkability and connectivity are central. Sidewalks throughout the development will be wide, well-lit, and landscaped, offering a comfortable and safe environment for walking, jogging, and biking. These pathways will connect key areas within the site, including residential zones, retail spaces, and public amenities, ensuring that all destinations within the community are easily accessible on foot.

To further enhance connectivity, the plan integrates access points to multiple trails that wind through and around the site. These trails will link green spaces, pocket parks, and natural areas, providing scenic routes for recreation and relaxation. Along these trails, residents will find benches, shaded rest areas, and viewpoints that allow them to take in the area’s natural beauty, promoting both active lifestyles and community engagement.

The interconnected sidewalk and trail system will also connect to La Vergne’s broader pedestrian and bike network, allowing easy access to surrounding neighborhoods, schools, and community centers. This design not only supports sustainability by reducing the need for car travel but also creates an inviting pedestrian experience that encourages residents and visitors to explore the area, fostering a vibrant, active community atmosphere.





VEHICULAR STREET ACCESS

The South Waldron Mixed Use Site has been strategically designed to integrate seamlessly with existing and planned infrastructure, promoting strong vehicular connectivity and accommodating anticipated traffic demands on key thoroughfares. The site will benefit from access to both the current and proposed improvements on Waldron Road and the future Blair Road Extension. To support traffic flow, the design incorporates primary, secondary, and tertiary street patterns within the development.

With the increased traffic expected from the South Waldron development, both Waldron Road and Blair Road are poised for enhancements by the City of La Vergne. Waldron Road is set to become a 3-lane roadway through realignment, with potential expansion to 5 lanes in the future, ensuring capacity for projected vehicular demands. Blair Road improvements include widening to 3 lanes, along with the installation of a traffic signal at the Waldron Road intersection. Additionally, Lake Road will be realigned to intersect with Waldron Road, facilitating smoother transitions and access points.

The South Waldron Mixed Use Site will feature four residential access points and include five commercial entrances onto Waldron and Blair Roads, equipped with designated travel lanes for efficient ingress and egress. An internal street network will promote connectivity within the development, as well as link to the surrounding roadways, providing accessible routes throughout.

All infrastructure will meet City of La Vergne Standards, with any deviations requiring approval from the City Engineer, ensuring that the development aligns with local regulations and supports community growth effectively.

ECONOMIC IMPACT OVERVIEW

One-Time Impact from Construction									
	Economic Impact	Direct/ Indirect Jobs	Wages	Indirect Local Sales Tax	Direct Local Sales Tax	Local Other Taxes	Indirect Property Tax	Direct Property Tax	Total Local Taxes & Fees
Construction	\$ 570,174,180	2,258	\$ 138,338,771	\$ 2,233,134	\$ 3,707,463	\$ 355,068	N/A	N/A	\$ 6,295,665
Annual Impact from Operations - At Full Operation									
Development Type	Economic Impact	Direct/ Indirect Jobs	Wages (Direct & Indirect)	Indirect Local Sales Tax	Direct Local Sales Tax	Local Other/Hotel Taxes	Indirect Property Tax	Annual Average Direct Property Tax (City/County Debt Service & Fees)	Total Local Taxes & Fees
Privately-Owned Residential	\$ 322,007	2	\$ 119,743	\$ 1,933	N/A	\$ 306	\$ 2,580	\$ 116,528	\$ 121,347
Multi-Family Residential	\$ 7,444,382	30	\$ 1,871,644	\$ 30,213	N/A	\$ 4,804	\$ 39,812	\$ 894,566	\$ 969,395
Hotel	\$ 7,463,960	38	\$ 1,162,218	\$ 18,761	\$ 120,780	\$ 332,383	\$ 49,868	All Commercial and Land Included in Total Above	\$ 521,792
Retail	\$ 234,214,657	1,478	\$ 47,960,274	\$ 774,199	\$ 3,449,916	\$ 123,098	\$ 1,951,599		\$ 6,298,812
Commercial Office	\$ 27,358,650	140	\$ 8,469,970	\$ 136,726	N/A	\$ 21,740	\$ 184,723		\$ 343,189
Medical Office	\$ 18,225,180	79	\$ 5,398,817	\$ 87,150	N/A	\$ 13,857	\$ 104,368		\$ 205,375
Total	\$ 295,028,837	1,767	\$ 64,982,666	\$ 1,048,982	\$ 3,570,696	\$ 496,187	\$ 2,332,951	\$ 1,011,094	\$ 8,459,911
20-Year Impact from Operations Plus One-Time Construction of Development									
Development Type	Economic Impact	Direct/ Indirect Jobs	Wages (Direct & Indirect)	Indirect Local Sales Tax	Direct Local Sales Tax	Local Other/Hotel Taxes	Indirect Property Tax	Direct Property Tax (City/County Debt Service and Fees)	Total Local Taxes & Fees
Privately-Owned Residential	\$ 6,440,148	2	\$ 2,394,852	\$ 38,653	N/A	\$ 6,121	\$ 51,600	\$ 2,330,566	\$ 2,426,941
Multi-Family Residential	\$ 148,887,648	30	\$ 37,432,873	\$ 604,260	N/A	\$ 96,077	\$ 796,249	\$ 17,891,318	\$ 19,387,905
Hotel	\$ 138,083,260	38	\$ 21,501,028	\$ 347,080	\$ 2,234,430	\$ 6,149,086	\$ 922,558	All Commercial and Land Included in Total Above	\$ 9,653,155
Retail	\$4,607,002,309	1,478	\$ 943,378,598	\$15,228,489	\$67,859,853	\$ 2,421,330	\$ 38,387,961		\$ 123,897,633
Commercial Office	\$ 519,814,350	140	\$ 160,929,430	\$ 2,597,803	N/A	\$ 413,051	\$ 3,509,743		\$ 6,520,597
Medical Office	\$ 346,278,420	79	\$ 102,577,525	\$ 1,655,858	N/A	\$ 263,281	\$ 1,982,993		\$ 3,902,132
Construction	\$ 570,174,180	Transient	\$ 138,338,771	\$ 2,233,134	N/A	\$ 355,068	N/A	N/A	\$ 6,295,665
Total	\$6,336,680,315	1,767	\$ 1,406,553,077	\$22,705,277	\$70,094,283	\$ 9,704,014	\$ 45,651,105	\$ 20,221,884	\$ 172,084,027

Benefit/Cost Ratio: (Ratio of Taxes Designated to TIF to Local Taxes Generated From Construction and Operations, as well as Taxes Designated for Debt Service and Admin Fees.)

Rutherford County and City of LaVergne Tax Summary					
Real Property					
Year	Net New Tax on Incremental Assessed Value	Total Tax Designated for Debt Service	Total Admin Fee	Total Designated to TIF	Total Remaining Taxes After All Designations
Year 1 - 2026	\$ 1,779,298	\$ 366,592	\$ 14,127	\$ 1,059,529	\$ 339,049
Year 2 - 2027	\$ 2,237,384	\$ 461,954	\$ 17,754	\$ 1,331,572	\$ 426,103
Year 3 - 2028	\$ 2,462,778	\$ 507,411	\$ 19,554	\$ 1,466,526	\$ 469,288
Year 4 - 2029	\$ 2,462,778	\$ 507,411	\$ 19,554	\$ 1,466,526	\$ 469,288
Year 5 - 2030	\$ 2,326,879	\$ 480,432	\$ 18,464	\$ 1,384,835	\$ 443,147
Year 6 - 2031	\$ 2,419,954	\$ 499,650	\$ 19,203	\$ 1,440,229	\$ 460,873
Year 7 - 2032	\$ 2,419,954	\$ 499,650	\$ 19,203	\$ 1,440,229	\$ 460,873
Year 8 - 2033	\$ 2,419,954	\$ 499,650	\$ 19,203	\$ 1,440,229	\$ 460,873
Year 9 - 2034	\$ 2,516,753	\$ 519,636	\$ 19,971	\$ 1,497,838	\$ 479,308
Year 10 - 2035	\$ 2,516,753	\$ 519,636	\$ 19,971	\$ 1,497,838	\$ 479,308
Year 11 - 2036	\$ 2,516,753	\$ 519,636	\$ 19,971	\$ 1,497,838	\$ 479,308
Year 12 - 2037	\$ 2,516,753	\$ 519,636	\$ 19,971	\$ 1,497,838	\$ 479,308
Year 13 - 2038	\$ 2,617,423	\$ 540,421	\$ 20,770	\$ 1,557,751	\$ 498,480
Year 14 - 2039	\$ 2,617,423	\$ 540,421	\$ 20,770	\$ 1,557,751	\$ 498,480
Year 15 - 2040	\$ 2,617,423	\$ 540,421	\$ 20,770	\$ 1,557,751	\$ 498,480
Year 16 - 2041	\$ 2,617,423	\$ 540,421	\$ 20,770	\$ 1,557,751	\$ 498,480
Year 17 - 2042	\$ 2,722,120	\$ 562,038	\$ 21,601	\$ 1,620,061	\$ 518,420
Year 18 - 2043	\$ 2,722,120	\$ 562,038	\$ 21,601	\$ 1,620,061	\$ 518,420
Year 19 - 2044	\$ 2,722,120	\$ 562,038	\$ 21,601	\$ 1,620,061	\$ 518,420
Year 20 - 2045	\$ 2,722,120	\$ 562,038	\$ 21,601	\$ 1,620,061	\$ 518,420
Total	\$ 49,954,160	\$ 10,311,126	\$ 396,430	\$ 29,732,276	\$ 9,514,328
Net Present Value**				\$ 16,637,893	


* Bold indicates reappraisal year where a 4% increase in value is assumed.

**Discount Rate of NPV Calculation is 6%



DEVELOPMENT INVESTMENT

COST IMPACT DISTRIBUTION



\$243,560,000
TOTAL COSTS



POTENTIAL MERCHANDISING PLAN

A strong tenant mix in a suburban mixed-use town center is critical for maximizing foot traffic, ensuring long-term sustainability, and driving economic success. The most important elements include:

Anchor Tenants

- Grocery Store or Specialty Market – A high-traffic grocer (e.g., Whole Foods, Trader Joe’s, or a regional chain) draws consistent daily visitors.
- Fitness Center or Boutique Gym – Health-conscious tenants (e.g., OrangeTheory, CycleBar) provide steady foot traffic.
- Entertainment Venue – A small movie theater or event space can create evening and weekend foot traffic

Food & Beverage Mix

- Casual Dining & Fast Casual – Popular chains or unique local spots (e.g., Panera, Shake Shack, or a chef-driven bistro).
- Cafés & Coffee Shops – A Starbucks, local roaster, or European-style café fosters social interaction and remote work.
- Bars & Breweries – Wine bars, breweries, or cocktail lounges encourage evening and weekend traffic.
- Grab-and-Go – Juice bars, bakeries, or dessert shops (e.g., Crumbl Cookies) create impulse visits.

Retail & Shopping

- Daily Needs & Convenience Retail – Drugstores, dry cleaners, and convenience stores provide essential services.
- Fashion & Lifestyle – A mix of national brands and local boutiques enhances the shopping experience.
- Home & Décor – Stores like West Elm, Pottery Barn, or a local home goods shop align with suburban lifestyles.
- Office & Professional Services
Coworking Spaces & Small Offices – WeWork-style spaces or traditional office tenants create daytime demand.
- Medical & Wellness Services – Urgent care, dental, and physical therapy clinics provide steady daytime visits.
- Financial & Legal Services – Banks, mortgage lenders, and law firms offer essential community services.

Residential & Hospitality Component

- Apartments or Condominiums – Mixed-income housing supports local businesses with built-in foot traffic.

Public & Community Spaces

- Parks, Plazas, & Event Spaces – Outdoor gathering areas encourage events, farmers’ markets, and seasonal activities.
- Cultural & Educational Tenants – Libraries, art galleries, or pop-up exhibition spaces enhance community appeal.

Experiential & Specialty Concepts

- Health & Beauty – Spas, nail salons, and wellness studios attract steady female foot traffic.
- Entertainment & Recreation – Escape rooms, VR arcades, or golf simulators add interactive elements.

Key Considerations for Success:

- Balanced Uses: Ensure synergy between residential, office, retail, and hospitality.
- Traffic Flow: Strategically place anchors and destination tenants to maximize visibility.
- Diversity & Uniqueness: A mix of national brands and local businesses creates an authentic community feel.
- Seamless integration with enhancing existing neighborhoods providing daily conveniences and expanding evening and weekend options enriching the experience for both long time and new residents.

POTENTIAL MERCHANDISING PLAN

DINING | GROCERY | SPECIALTY

FAST CASUAL DINING

- Tazikis Mediterranean Cafe
- Velvet Taco
- Desaneos Pizza
- Slim and Husky
- Martin's BBQ Joint
- Shake Shack
- Smash Burger
- Hugh Babies
- Edley's BBQ
- Prince's Hot Chicken
- Corner Pub
- In Town Golf
- City BBQ
- Clyde's HiFi
- Moe's Southwest Grill
- Chipotle Mexican Grill
- Panera
- The Picnic Cafe
- Jimmy John's
- Hattie B's Hot Chicken
- Jack Browns

SIT DOWN DINING

- Blue Fish
- Del Friscos
- Burger Up
- Dough Baby
- Magianos Italian Classics
- Stir
- State of Confusion
- Balter Beerworks
- Thai Ensane
- Strawberry Alley
- The Mailroom
- Sperry's Restaurant
- Fleming's
- Stoney River
- Uncle Julio's
- Superica

BREWERY / WINE / BARS

- Black Abbey
- Bearded Iris
- Tail Gate
- YeeHaw
- Vino Fiesta
- Carolina Brewery
- Top of the Rock
- Sixty Vines

COFFEE

- Starbucks
- Black Rifle
- Coffee Ya'll
- Dose
- Frothy Monkey

DESSERTS

- Jeni's Ice Creams
- Nothing Bunt Cake
- No Bake Cookie Dough
- Sweet Cici's
- Godiva
- Jamba Juice
- Planet Smoothie

GROCERY

- Publix
- Whole Foods
- Sprouts
- Fresh Market
- Food City



*THIS IS A SAMPLING OF PROSPECTIVE TENANTS THAT WILL BE TARGETED FOR THE DEVELOPMENT AND IN NO WAY SHALL BE CONSTRUED AS A COMMITMENT FROM THESE COMPANIES IN THE DEVELOPMENT.

POTENTIAL MERCHANDISING PLAN

COMMERCIAL / MIXED USE DISTRICT



* THIS IS A SAMPLING OF PROSPECTIVE TENANTS THAT WILL BE TARGETED FOR THE DEVELOPMENT AND IN NO WAY SHALL BE CONSTRUED AS A COMMITMENT FROM THESE COMPANIES IN THE DEVELOPMENT.

POTENTIAL MERCHANDISING PLAN

HEALTH AND WELLNESS | SOFT GOODS

SOFT GOODS

- Binks Outfitters
- Lulu Lemon
- Kendra Scott
- J. McLaughlin
- White’s Mercantile
- Peter Millar
- Hemline Woodway
- Lizard’s Thicket
- fab’ rik
- Katy’s Hallmark
- Monkee’s
- REI Co-Op
- Serendipity
- Draper James
- Finnleys

HEALTH AND WELLNESS

- Hand and Stone Massage and Facial
- The Cosmetic Market
- Ulta Beauty
- Sephora
- Manduu Pulse Fitness
- Pure Barre
- Pure Sweat and Float studio
- Orange Theory
- Cycle Bar
- Club Pilates
- Lash Lounge
- European Wax Center
- Salons by JC
- Paul Mitchell Salon
- Elan Skin Care
- Skoah Facial Shop
- Massage Envy
- The Lotus Room
- Fitness Anytime
- Escape Day Spa + Salon




* THIS IS A SAMPLING OF PROSPECTIVE TENANTS THAT WILL BE TARGETED FOR THE DEVELOPMENT AND IN NO WAY SHALL BE CONSTRUED AS A COMMITMENT FROM THESE COMPANIES IN THE DEVELOPMENT.

POTENTIAL MERCHANDISING PLAN

HEALTH AND WELLNESS | SOFT GOODS



* THIS IS A SAMPLING OF PROSPECTIVE TENANTS THAT WILL BE TARGETED FOR THE DEVELOPMENT AND IN NO WAY SHALL BE CONSGTRUED AS A COMMITMENT FROM THESE COMPANIES IN THE DEVELOPMENT.



R.O.W. EXHIBIT

R.O.W. DEDICATION

The South Waldron Mixed Use Site is strategically positioned to leverage existing and planned infrastructure improvements as outlined in the City of La Vergne’s 2040 Comprehensive Transportation Plan (CTP). This alignment ensures enhanced connectivity and accessibility for both residents and businesses within the development.

Access and Infrastructure Compliance

The development will have access to existing public rights-of-way via proposed entrances on Waldron Road and future Blair Road improvements. All infrastructure will adhere to City of La Vergne standards, with any exceptions requiring approval from the City Engineer.

Planned Roadway Improvements

The CTP details specific projects aimed at upgrading key roadways adjacent to the development:

- Waldron Road: Currently a two-lane roadway without curbs or sidewalks, Waldron Road is slated for realignment under CTP Projects 1 and 2. These projects aim to enhance traffic flow and safety in the area.
- Lake Road: Also a two-lane roadway lacking curbs or sidewalks, Lake Road is set to receive improvements, including the addition of 2-foot shoulders, as specified in CTP Project 15. These enhancements will improve vehicular and pedestrian safety.
- Blair Road: Currently a two-lane roadway without curbs or sidewalks, Blair Road is planned for improvements under CTP Project 40. These upgrades will support increased traffic volumes and improve overall accessibility.

Development Integration

The South Waldron Mixed Use Site’s design incorporates primary, secondary, and tertiary street patterns to facilitate strong vehicular connectivity. The internal street network will provide seamless access throughout the development and to the surrounding roadways, aligning with the city’s transportation objectives.

By integrating these planned infrastructure improvements, the South Waldron Mixed Use Site will contribute to a more connected and accessible community, supporting La Vergne’s growth and development goals.

DEVELOPMENT STANDARDS

RESIDENTIAL

- Uses Permitted:**
- Single family detached homes shall be on its own lot of record and sold fee simple.
 - Townhomes shall be its own land record as fee simple or horizontal property regime.
 - Multifamily dwelling units shall be for rent.
- Residential Development Standards:**
- Entrances off of Waldron Road and Blair Road shall have new entrance signage constructed of masonry materials and anchored by landscaping.
 - Building heights shall not exceed 4 stories in height.
 - Builders shall install sod and landscaping along foundations of all primary and secondary front yards along R.O.W.s of all buildings. Seed/Straw will be installed on the side and rear foundations of all buildings.
 - All townhome buildings shall be comprised of fifty percent masonry and brick.
 - All mechanical equipment (i.e. HVAC and transformers) to be screened and located in the rear/side of all units.
 - All on-site utilities shall be underground.
 - All unit types will be serviced by a 3rd party trash company.
 - Prior to construction plan review, a complete and thorough design of the stormwater management system and facilities will be completed.
 - Parking for the residential units will comply with the City of La Vergne requirements.
 - Residential units shall have a mix of concrete and asphalt driveways.
 - All streets will be classified as a mix of public rights-of-way or private drives.
 - All streets have been designed to comply with City of La Vergne Streets Standards.
 - Public sidewalks will be provided on both sides of all public streets throughout the development to create a pedestrian friendly community. There will also be pedestrian connections between the residential portion of the development to the mixed uses town center.
 - Mail service will be provided via CBU.
 - Decorative street lights will be coordinated with MTEM.
 - All home owners shall be required to be a member of the H.O.A.
 - As a member of the H.O.A., the residents shall be subject to restrictive covenants, and be required to pay membership dues as determined by a 3rd party management company.
 - HOA will be managed by independent 3rd party management company.
 - The common areas will be owned and maintained by an H.O.A.
 - All infrastructure shall comply with City of La Vergne Standards. Any exceptions must be approved by the City Engineer.
 - Fencing shall be constructed of durable materials. Wooded and chain-link fences are prohibited.
 - All parking shall be located at least 10-feet from the public R.O.W. along Waldron and Blair Road.
 - All parking areas to be screened from public rights-of-way by landscaping or in combination with berms.
 - A mix of Type 1 & Type 2 Transitional Screening applications shall be provided at the perimeter edges of the proposed development and as identified/labeled.
 - Monument signage shall be placed no closer than 5-ft to the R.O.W. along Waldron and Blair Roads.
 - Monument signage shall have materials consistent with the building architecture, and be accented with landscaping. Signage lighting will be exterior or push-thru style illumination. Signage shall comply with applicable zoning ordinance at the time of request.
 - All mechanical equipment located on the ground (i.e. hvac and transformers) to be screened with landscape or fencing. If mechanical equipment is located on the roof, then they shall be screened from view.
 - Any solid waste enclosures shall be constructed of materials consistent with building architecture, be at least 8-feet tall, with opaque gates, and shall be screened with landscaping. Solid waste collection service shall be provided by a private hauler.
 - All on-site utilities will be underground.
 - On-site lighting will comply with the LZ-2 standards outlined in the Model Lighting Ordinance by the International Dark-Sky Association to prevent light pollution and provide safety for patrons and employees.
 - Parking will comply with the City of La Vergne Zoning Ordinance for the allowable uses outlined to the right. Shared parking shall be implemented as needed/requested.
 - All parking will have curbing.
 - Fencing shall be constructed of durable materials. Wooded and chain-link fences are prohibited.

COMMERCIAL

- While the exact uses for the commercial properties are unknown at this time, the allowable uses for this development are listed below. The list of allowable uses is based on the allowable uses listed under (C-2) Highway Service District and (C-3) Neighborhood Service Business District in the current zoning ordinance. Therefore, additional standards for those anticipated uses have been outlined below. The proposed sites will provide for adequate parking (including shared parking), vehicular and pedestrian circulation, solid waste management, stormwater management and landscaping.
- Uses Permitted:**
- Convenience retail sales and services
 - Consumer Repair Services
 - Financial, insurance, real estate and consulting services
 - Food and beverage services
 - Food Service (take out and drive-thru)
 - Animal Care & Veterinarian (provided no outside housing of animals)
 - General business services
 - General personal services
 - General retail trade
 - Medical Services
 - Professional Services (not otherwise listed)
 - Religious facilities
 - Daycare
 - Grocery Stores
 - Gasoline Station (including beer and tobacco sales)
 - Beauty Parlor
 - Barbershops
 - Hardware Store
 - Drug Store & Pharmacy
 - Liquor Store
 - Hotel
 - Professional Office
- Uses Prohibited:**
- Bus transit station
 - Bus or truck vehicle repair, meaintenance or storage facility
 - Building materials and farm equipment sales
 - Concrete or asphalt plant
 - Rock quarry
 - Residential homes leased on a short term basis of less than 30 days, such as VRBO and Air B&B, but hotels and motels are expressly permitted
 - Automobile sales, rental (other than as part of a hote's services) and delivery, aircraft dealers, boat dealers, recretaional and utility trailer dealers
 - Wholesale sales
 - Plant and forest nurseries
 - Mortuaries, crematoriums and funeral homes
 - Self-Storage, Mini Storage and Mini-Warehousing
 - Outside kennels/Stables
 - Manufacturing, Industrial and Warehousing
 - Sporting and recreational vehicle campgrounds and tracks
 - Automotive Repairs & Service
 - Cellular Towers over 25’ tall
 - Automotive wrecking & recycling
 - Junk or salvage yards
 - Vehicle Storage Areas
 - Truck Terminals
 - Automotive, marine craft, aircraft and accessories
 - Self-Service Laundries
 - Marijuana Dispensoary and/or Marijuana Paraphernalia
 - Beer & Tobacco Store (but spcifically excluding convenience retail sales, grocery, and services)
 - Vape/CBD Tattoo or Check Cashing Store
- Commercial Development Standards:**
- Building heights shall not exceed 4 stories in height.
 - All parking shall be located at least 10-feet from the public R.O.W. along Waldron and Blair Road.
 - All parking areas to be screened from public rights-of-way by landscaping or in combination with berms.
 - A mix of Type 1 & Type 2 Transitional Screening applications shall be provided at the perimeter edges of the proposed development and as identified/labeled.
 - Drive-thru windows shall be permitted for uses such as restaurants, financial institutions, dry cleaners, etc.
 - Commercial buildings shall have a well defined architectural base by use of different materials, colors or change in pattern or a combination of these techniques.
 - Building elevations will have articulation or multiple building planes to promote quality architecture, and main entrances that are well defined and easily recognizable.
 - Buildings shall have a minimum of 3’ of foundation planting, except where access for drive-through windows are needed.
 - The commercial lots shall have a pedestrian network that connects to Waldron Road and Blair Road. There will also be pedestrian connections between the residential portion of the development from the commercial property.
 - Monument signage shall be placed no closer than 5-ft to the R.O.W. along Waldron and Blair Roads.
 - Monument signage shall have materials consistent with the building architecture, and be accented with landscaping. Signage lighting will be exterior or push-thru style illumination. Signage shall comply with applicable zoning ordinance at the time of request.
 - Building signage shall follow standards outlined in the City of La Vergne sign ordinance.
 - All mechanical equipment located on the ground (i.e. hvac and transformers) to be screened with landscape or fencing. If mechanical equipment is located on the roof, then they shall be screened from view.
 - Any solid waste enclosures shall be constructed of materials consistent with building architecture, be at least 8-feet tall, with opaque gates, and shall be screened with landscaping. Solid waste collection service shall be provided by a private hauler.
 - All on-site utilities will be underground.
 - On-site lighting will comply with the LZ-2 standards outlined in the Model Lighting Ordinance by the International Dark-Sky Association to prevent light pollution and provide safety for patrons and employees.
 - Parking will comply with the City of La Vergne Zoning Ordinance for the allowable uses outlined to the right. Shared parking shall be implemented as needed/requested.
 - All parking will have curbing.
 - Commercial lots will not be a part of the residential H.O.A.
 - Commercial lots that utilize communal facilities shall be part of an owners organization responsible for the care and upkeep of shared drainage, parking, etc.

ARCHITECTURAL CHARACTERISTICS - TOWNHOMES AND MULTIFAMILY/SENIOR HOUSING

ROOFING MATERIALS

PERMITTED	DIMENSIONAL ASPHALT SHINGLES LAMINATED SHINGLES COPPER FINISHES STANDING SEAM METAL ROOFS
NOT PERMITTED	ROLLED ASPHALT ASBESTOS CEMENT SHINGLES BRIGHTLY COLORED METAL ROOFING


EXTERIOR SIDING MATERIALS

PERMITTED	BRICK STONE STUCCO NATURAL WOOD ACCENTS CEMENTITIOUS PANELS + LAP/PLANK SIDING
NOT PERMITTED	ALL PLASTICS/VINYL SIDING PLYWOOD CONCRETE BLOCK


EXTERIOR COLORS

PERMITTED	MUTED NATURAL EARTH TONES
NOT PERMITTED	BRIGHT PRIMARY COLORS

TOWNHOMES



Width: Ranges from 16-20 feet
Depth: Range from 70 - 120 feet
Front Yard Setback: 10 feet
Front Facade Zone: 10 feet
Side Street Setback (Corner Lots): 10 feet.
Side Street Facade Zone (Corner Lots): 10 feet
Side Yard Setback: Townhomes must be at least 10 feet apart.
Rear Loaded Garages: May be placed at either 5 feet or 22 feet from the edge of the alley, and within the side facade zones.
Porches, Bay Windows, and Stoops: May extend into the Front Yard Setback, but no closer than 5 feet to sidewalk
Front loading townhomes shall provide either surface parking spaces along the front facade with a sidewalk and a minimum 5 foot landscape to front facade, or front loading garages set back 5 feet from the main entrance and provide a minimum 22' driveway parking space from back of sidewalk to face of garage.
Townhomes shall be its own land record as fee simple or horizontal property regime.



ARCHITECTURAL CHARACTERISTICS - SINGLE FAMILY DETACHED HOMES

ROOFING MATERIALS

PERMITTED	DIMENSIONAL ASPHALT SHINGLES LAMINATED SHINGLES COPPER FINISHES STANDING SEAM METAL ROOFS
NOT PERMITTED	ROLLED ASPHALT ASBESTOS CEMENT SHINGLES BRIGHTLY COLORED METAL ROOFING


EXTERIOR SIDING MATERIALS

PERMITTED	BRICK STONE STUCCO NATURAL WOOD ACCENTS CEMENTITIOUS PANELS + LAP/PLANK SIDING
NOT PERMITTED	ALL PLASTICS/VINYL SIDING PLYWOOD CONCRETE BLOCK



EXTERIOR COLORS

PERMITTED	MUTED NATURAL EARTH TONES
NOT PERMITTED	BRIGHT PRIMARY COLORS

SINGLE FAMILY



Width: Ranges from 50 - 75 feet
Depth: Range from 110 - 130 feet
Front Yard Setback: 10 feet
Front Facade Zone: Generally 10 - 20 feet deep.
Side Street Setback (Corner Lots): 10 feet.
Side Street Facade Zone (Corner Lots): 10 feet.
Side Yard Setback: Minimum setbacks for all structures are 5 feet. Houses must be at least 10 feet apart
Garages: Lots with driveway access from the street shall have garages placed min. 3 feet behind the front facade of the Main Body of the house.
Porches, Bay Windows, and Stoops: May extend into the Front Yard Setback, but no closer than 5' to sidewalk.



ARCHITECTURAL CHARACTERISTICS - COMMERCIAL

ARCHITECTURAL CHARACTER STANDARDS:

- Elevated Architectural Detail
- Cohesive Design Aesthetic for All Buildings
- Similar Themes between adjacent Structures
- Rooflines and Cornices to vary to create interest
- Mechanical Screening from Pedestrian View
- Color Scheme to be consistent within General Design
- One and Two-Level Structures to be comparable in heights with roof lines and features
- Glazing at the main retail spaces on the main level is beneficial for pedestrian interest
- Building and Dumpster enclosure elevations sown with materials notes and colored to accurately represent built appearance
- Prototype designs, indicate how they have been adapted to La Vergne setting and guidelines
- Location of building service areas noted, with screening provided
- Location of exterior mechanical equipment noted, plans for screening

MASSING, PROPORTION AND SCALE:


- Create appropriate massing and scale per adjacent structures and context
- Awnings, canopies and Main level retail window openings
- Vertical masonry columns between glazing
- Common design elements with masonry
- Utilize nominal masonry and not utility sized brick
- Main level window height to be 10'-0" with clear glazing
- Building entries to be visible and defined
- Facades shall not be flat and shall have stepping and breaks

BUILDING HEIGHT AND SETBACKS:

- All architectural building design shall follow the La Vergne City Zoning and Design Ordinance
- Roof cornices shall create shadow lines
- Clock tower and Roof features such as Gables and Tower Features shall be provided at main corner elements
- Symmetrical building heights and roof features may be required at gateway elements between buildings
- One story and two story shall be designed not to create drastic building height changes
- Setbacks with entrances and differentiating setbacks within buildings is encouraged for shadowing etc.
- Mechanical roof screening with parapets, roof structures or placed where not visible from grade
- No long Roof line designs will be appropriate without variation in parapets and cornices

BUILDING COMPOSITION AND PATTERNING:

- Repetition is good for patterning
- Mix of masonry and metal panels and sim. limestone
- Create pedestrian visual connections between structures
- Symmetry should be used in mirrored building structures for "gateway" effect
- Roof line should be designed to vary and provide rhythm
- No large wall areas without varying depths and breaks in elevation
- Windows, Columns and vertical elements to break up facades
- Lighting sconces and other lighting features to be used
- Base, Body and Cap for architectural standards
- Main Level Retail windows areas to be 40% min.



ARCHITECTURAL CHARACTERISTICS - COMMERCIAL

MATERIAL SELECTIONS AND STANDARDS AND PERCENTAGES:

- All visible Sides of buildings shall be consistent for material use.
- All materials to be durable and of high quality for longevity and maintenance purposes
- PRIMARY MATERIALS – 70%: Nominal Full brick or thin brick
Natural or Simulated/Synthetic Stone
Smooth Cast Stone
- SECONDARY MATERIALS – 20%: Exterior Insulation Finish System or EIFS (Cornices etc.)
Authentic Stucco
ACM Reynobond Smooth Metal Panels
Composite or Cementuous Panels
- ACCENT MATERIALS – 10%: [NOTE: No More that 10% of Accent Material is Allowed]
Architectural Metal Wall Panels
Simulated Prefinished Wood
Smooth-Faced Concrete Masonry
Simulated stone (Lick and Stick)
CMU or Split-Faced CMU
Corrugated R-Panels (Prefab Structures)
- DISCOURAGED MATERIAL USE:
Large areas of EIFS/Dryvit
Simulated stone (Lick and Stick)
CMU or Split-Faced CMU
Corrugated R-Panels (Prefab Structures)

WINDOWS:

- 1” Insulated Aluminum Storefront Marvin Elevate or Equal
- Iron Lion Metal Frame or Equal
- False Windows and Spandrel Glass may be used as accent

ROOFING:

- Standing Seam Metal Roofing
- Pre- Finished Metal Coping
- TPO for typical non-visible roofing

AWNINGS AND CANOPIES:

- Standing Seam Metal Awnings
- Smooth ACM Metal for Canopies etc.
- Fabric Awnings

LIGHTING:

- Consistent Pole Type Lighting, Black in Color
- Sconce Lighting, should have varying standards
- Uplighting recessed in walkway or building mounted accent

GENERAL PALETTE:

- Retail/Mixed use, along center entry drive or “Avenues” architectural aesthetic may have a similar aesthetic to create a more cohesive well-organized shopping environment.
- Commercial outparcels and other structures would follow the primary and secondary material options.
- Prototype retail parcels would follow the primary and secondary material options but allow the prototypical design and their material concepts to remain.
- “Avenue” or retail/Mixed use section may be lighter stucco and brick with main level glazing
- Colors for accents may be placed for interest or signage
- Number of varying colors may be limited depending on tone changes
- Lighting and window type frames to be considered

HARDSCAPES:

- Masonry site landscape and seat walls, planter walls and landscape features to create pedestrian gathering spaces with benches and light poles along walkways.
- Pathways to be added from parking to retail spaces

ROOF AND PARAPET:

- Long facades should have vertical features and varying roof lines
- Cornice lines with masonry detail shadow lines
- Gable roof and Corner Tower Features with varying roof lines
- Parapets and cornices shall create detail and provide shadowing
- Metal Roofing features and coping detail shall be consistent
- Stepping facades in plan and roof line
- Varying heights
- Rear roof side parapets visible form grade shall have finished material all sides
- Roof pitch in all areas shall be the same pitch for consistency

SIGNAGE:


- All building signage shall follow the La Vergne City Zoning and Design Ordinance
- Signage should be contextual in height and scale with neighboring or adjacent structures
- Way finding signage will be designed to be throughout the development with a consistent aesthetic
- Neon Signage is not encouraged outside of “OPEN” type at retail storefronts





Subdivision Name	TYPE	Existing 2024	Proposed Build-out	Exiting Plus Permitted
Cedar Ridge Apt	Apartment	150	150	150
Farmingdale	Single Family	267	267	267
Dove Creek	Single Family	133	133	133
Carother's Crossing (Metro)	Mixed Use	414	2300	414
Carother's Crossing (La Vergne)	Mixed Use	166	343	210
Brookside	Single Family	189	198	189
Summit View	Single Family	117	117	117
Woodland Hills	Single Family	366	451	366
Walnut Ridge	Single Family	68	68	68
The Ridge	Single Family	112	145	117
Arbor Ridge	Mixed Use	0	571	0
Portico Place	Single Family	71	163	87
Woodsong	Single Family	208	208	208
Vineyards	Single Family	353	353	353
McFarlin Point	Single Family	350	350	350
Pinnacle Point	Single Family	120	143	120
Woods at Martins Bend	Single Family	32	32	32
Gwynne Farms (Smyrna)	Mixed Use	135	540	135
Mission Hills	Mixed Use	0	599	0
Blair Ridge	Townhome	0	141	0
	Total:	3251	7272	3316

Population Summary		Household Summary	
2010 Total Population	32,888	2010 Households	11,049
2020 Total Population	38,719	2010 Average Household Size	2.98
2023 Total Population	40,760		
2028 Total Population	43,518	2020 Total Households	12,472
		2020 Average Household Size	3.10
2023-2028 Annual Rate	1.32%		
2023-2028 Total Growth	6.60%	2023 Households	13,170
		2023 Average Household Size	3.09
2020 Group Quarters	61		
2023 Group Quarters	61	2028 Households	14,095
		2028 Average Household Size	3.08
2023 Total Daytime Population	37,307	2023-2028 Annual Rate	1.37%
Workers	17,469		
Residents	19,838	2010 Families	8,523
		2010 Average Family Size	3.34
		2023 Families	9,668
		2023 Average Family Size	3.55
		2028 Families	10,296
		2028 Average Family Size	3.54
		2023-2028 Annual Rate	1.27%
Housing Unit Summary			
2023 Housing Units	13,653		
Owner Occupied Housing Units	68.8%		
Renter Occupied Housing Units	27.6%		
Vacant Housing Units	3.5%		
2028 Housing Units	14,597		
Owner Occupied Housing Units	71.0%		
Renter Occupied Housing Units	25.6%		
Vacant Housing Units	3.4%		




SUBDIVISION MAP

EXISTING SUBDIVISIONS

The South Waldron Mixed Use Site is centrally located amidst a diverse array of residential subdivisions, each contributing to the area's established character and appeal.

- East: Arbor Ridge PDR along Waldron Road offers a mix of residential types, commercial spaces, and trails. Further east, Ivy Pointe consists of two-story, single-family homes with garages and brick facades.
- North: Walnut Ridge Estates on Walnut Ridge Drive features single-family homes, primarily one and two stories, with vinyl and brick exteriors.
- West: The Ridge includes two-story single-family homes with garages and brick facades.
- Northwest: Carothers Crossing offers two-story homes with front and rear garages, featuring brick and stone exteriors.
- South: Pinnacle Point Subdivision, located behind Rock Springs Elementary, consists of two-story single-family homes.

This mix of established subdivisions enhances the South Waldron Mixed Use Site's potential for seamless integration of commercial and retail development as part of the local residential fabric, provides a well-rounded, community-oriented environment. With architectural consistency, and frequent use of brick and stone, combined with accessible amenities, positions the development as a complementary addition to the surrounding neighborhoods.



EXISTING ZONING

The South Waldron Mixed Use Site is Located in a diverse zoning area within La Vergne, the site brings together residential and commercial opportunities to create a thriving community-oriented environment. The surrounding area is largely zoned Low Density Residential (R-1), preserving the peaceful and residential character of the neighborhood while offering a seamless integration for commercial development.

Proximity to Planned Development Residential (PDR) Areas:



- Carothers Crossing (Northwest of the site): This PDR-zoned area provides a unique community feel with a blend of housing types, creating a versatile neighborhood that fosters interaction and accessibility. The mixed residential styles within Carothers Crossing attract a dynamic community that would benefit from nearby commercial conveniences.
- Arbor Ridge (East, along Waldron Road): Another PDR-zoned area, Arbor Ridge combines diverse residential options with amenities like trails and open spaces, supporting an active, walkable environment. This development emphasizes community connectivity, making it a natural fit for businesses that value foot traffic and neighborhood engagement.

This mix of R-1 and PDR zoning around the South Waldron site offers a balanced array of land use options, promoting a harmonious blend of residential density and commercial accessibility. The integration of these zoning types encourages connectivity, providing residents with easy access to essential services, retail options, and amenities. The site's proximity to these mixed-use and residential areas makes it an ideal location for businesses aiming to serve a well-established and growing community, ultimately enhancing the neighborhood's appeal and functionality.


EXISTING ZONING MAP - CITY OF LA VERGNE

SITE UTILITIES

- Water Service will be provided by the City of La Vergne Public Utilities Department.
- As part of the Blair Road extension project, a 12" and 8" water main will be extended through the northern half of the property. As a part of the Waldron Road widening project, the existing 12" and 8" water mains will eventually be replaced by a single 18" water main.
- Sanitary sewer exists in the northern half of the project boundary along side Hurricane Creek, a 12" gravity main for a portion of the limits before upsizing to an 18" gravity sewer main. The southern half of the project is currently served by a lift station, gravity connections are currently being explored.
- Electric Service will be provided by Middle Tennessee Electric Membership Corporation, MTEMC. Service will be extended from Waldron Road into all areas of the site.



SITE UTILITY EXHIBIT




SITE TOPOGRAPHY


- The topographic map above shows the site's topographic contours and general drainage patterns in the existing condition.
- The northern portion of the site drains east to west towards Hurricane Creek, which runs south to north. The southern portion of the project drains west to east and south to north.
- This property does not lie within any floodplain areas and is fully within Zone "X" as shown on panel 47149C0105J, EFF. 5/9/2023.

LEGEND

- EXISTING 10' CONTOUR
- ← STORMWATER FLOW DIRECTION
- - - - - PROPERTY BOUNDARY



HYDROLOGY AND TOPOGRAPHY



EP^{co}



SITE SURVEY

The South Waldron Mixed Use Site is meticulously planned to harmonize with its surrounding environment while providing a high-quality aesthetic that supports retail, commercial, and community engagement. The design incorporates key architectural elements to create a welcoming and cohesive space that aligns with nearby structures, enhancing the area's overall character and appeal.

Proposed Site Work Elements:

- **Massing and Scale:** The building forms will be thoughtfully scaled and massed to match the context of adjacent structures, ensuring compatibility with the surrounding neighborhood.
- **Awnings, Canopies, and Retail Window Openings:** Ground-level retail spaces will feature awnings and canopies to add depth to the façade while providing shelter for patrons. Large retail windows will foster visibility and a welcoming ambiance, inviting pedestrian engagement and street activity.
- **Vertical Masonry Columns:** Vertical masonry columns between window glazing provide a rhythm and solidity to the structure, enhancing its architectural integrity and visual appeal.
- **Masonry Design Consistency:** Common design elements will include high-quality masonry detailing, incorporating nominal-sized bricks (not utility-sized) to ensure refined, cohesive design. This masonry approach strengthens the building's presence while promoting durability and timeless appeal.
- **Main Level Windows with Clear Glazing:** Large 10-foot high clear-glazed windows on the main level will increase natural light, support visual connections to the interior, and create an open and transparent atmosphere for retail spaces.
- **Defined Building Entries:** The entrances will be highly visible and thoughtfully defined, creating an inviting and accessible entry experience for customers and visitors.
- **Dynamic Facade Design:** To avoid flat facades, the buildings will feature architectural stepping and breaks that add depth and interest, promoting a varied and visually engaging streetscape. This articulation creates a human scale and ensures that the development complements the surrounding area's architectural diversity.

These design and site work elements come together to create a visually appealing, functional, and community-oriented development that enhances the local architectural landscape while supporting businesses and community interaction.

Line Table		
Line #	Direction	Length
L1	S08° 58' 31" W	41.20'
L2	S08° 21' 17" W	118.97'
L3	S08° 00' 17" W	49.68'
L4	N82° 23' 01" W	231.77'
L5	N06° 41' 29" E	152.28'
L6	N76° 05' 41" W	80.86'
L7	N08° 39' 15" E	140.13'
L8	S81° 19' 11" E	40.45'
L9	N08° 37' 55" E	97.36'
L10	N08° 40' 09" E	100.00'

Line Table		
Line #	Direction	Length
L11	N08° 40' 47" E	100.02'
L12	N10° 34' 07" E	24.56'
L13	N10° 34' 07" E	75.13'
L14	N81° 31' 20" W	152.03'
L15	N75° 21' 15" W	50.00'
L16	N19° 36' 48" E	30.73'
L17	N81° 21' 20" W	152.82'
L18	S75° 52' 08" W	62.10'
L19	N60° 00' 51" W	103.94'
L20	N61° 35' 37" W	57.19'

Line Table		
Line #	Direction	Length
L21	N19° 12' 06" E	217.46'
L22	N38° 56' 35" W	148.60'
L23	N11° 21' 07" W	54.97'
L24	N45° 31' 30" W	137.19'
L25	S40° 12' 09" W	65.87'
L26	S42° 34' 30" W	72.93'
L27	S37° 43' 40" W	146.97'
L28	S06° 41' 10" W	74.83'

Curve Table				
Curve #	Radius	Length	Chord Direction	Chord Length
C1	250.00'	21.82'	N17° 08' 47" E	21.81'

SITE SURVEY


PLANT PALETTE



OCTOBER GLORY
MAPLE
*Acer rubrum 'October
Glory'*
Fall color: Red
Deciduous Tree



WILDFIRE BLACK
GUM
Nyssa sylvatica 'Wildfire'
Fall color: Red/Orange/Purple
Deciduous Tree
Bloom: White; Spring
Fruit: Black; Fall



SHUMARD OAK
Quercus shumardii
Fall color: red
Deciduous



HIGHTOWER WILLOW
OAK
Quercus phellos 'QPSTA'
PP13,677
Fall color: Orange/Yellow
Deciduous



RIVER BIRCH
Betula nigra
Fall color: Yellow
Deciduous



MOONGLOW
SWEETBAY MAGNOLIA
*Magnolia virginiana 'Jim
Wilson'*
Fall color: Green
Semi-Evergreen
Bloom: White; Summer



RISING SUN REDBUD
*Cercis canadensis 'Rising
Sun'*
Fall color: Red/Orange
Deciduous
Bloom: Pink; Spring
Fruit: Dark brown pod; Winter



APPALACHIAN
SPRING DOGWOOD
*Cornus florida
'Appalachian Spring'*
Fall color: Red/Purple
Deciduous
Bloom: White; Spring



AMERICAN HOLLY
Ilex opaca
Fall color: Green
Evergreen
Fruit: Red; Fall to Winter



GREEN GIANT
ARBORVITAE
*Thuja occidentalis 'Green
Giant'*
Fall color: Green
Evergreen



NELLIE STEVENS
HOLLY
Ilex x 'Nellie R Stevens'
Fall color: Green
Evergreen Shrub
Bloom: White; Spring
Fruit: Red; Fall to Winter



EMERALD
ARBORVITAE
*Thuja occidentalis
'Emerald'*
Fall color: Green
Evergreen Tree



SKY PENCIL
JAPANESE HOLLY
Ilex crenata 'Sky Pencil'
Fall color: Green
Evergreen Shrub
Bloom: White; Spring
Fruit: Black; Fall to Winter



HOOGENDORN
JAPANESE HOLLY
Ilex crenata 'Hoogendorn'
Fall color: Green
Evergreen Shrub
Bloom: White; Spring
Fruit: Black; Fall to Winter



CARISSA HOLLY
Ilex cornuta 'Carissa'
Fall color: Green
Evergreen Shrub
Bloom: White flower; Spring
Fruit: Red; Fall to Winter



SHAMROCK
INKBERRY
Ilex glabra 'Shamrock'
Fall color: Green
Evergreen
Bloom: White; Spring
Fruit: Black; Winter to Spring



LITTLE LIME
HYDRANGEA
*Hydrangea paniculata
'Little Lime'*
Fall color: Pink/Burgundy
Deciduous
Bloom: Light green; Summer



WALKERS LOW CATMINT
*Nepeta x Faassenii
'Walker's Low'*
Fall color: Red/Orange
Herbaceous Perennial
Bloom: Purple; Spring to Fall



OAKLEAF HYDRANGEA
Hydrangea quercifolia
Fall color: Red/Maroon
Deciduous
Bloom: White; Spring to Summer



VIRGINIA SWEETSPIRE
Itea virginica
Fall color: Red/Maroon
Deciduous
Bloom: white; Spring to Summer



ARROWWOOD
VIBURNUM
*Viburnum dentatum
'Arrowwood'*
Fall color: Red/Orange
Deciduous
Bloom: White; Spring
Fruit: Black; Fall



CASSIAN FOUNTAIN
GRASS
*Pennisetum alopecuroides
'Cassian's Choice'*
Fall color: Gold/Yellow
Deciduous
Bloom: Cream Pink; Summer



AUTUMN FERN
*Dryopteris erythosora
'Brilliance'*
Fall color: Red/Orange/Green
Evergreen

VISION IMAGERY

SOUTH WALDRON ROAD MIXED USE DEVELOPMENT





Item #: 4. **Item Title: Recommendation to the Board of Mayor and Aldermen for Subdivision Acceptance - Portico Place, Section 2, Phase 2 and Resubdivision of Common Areas A & B of Section 2, Phase 1. Requested by SEC, Inc. Property located off Blair Road (Tax Map 29, Parcel 20.04). PDR (Planned Density Residential) Zoning District.**

Reviewed By:
Bo Logan, City Planner
Gary Lide, City Engineer

Summary:

The applicant requests subdivision acceptance for Portico Place, Section 2, Phase 2 and Resubdivision of Common Areas A & B of Section 2, Phase 1.

This request is comprised of 52 lots on 15.69 acres.

Staff Comments / Technical Items:

Planning (Bo Logan - blogan@lavernetn.gov; and Jake Blair - jblair@lavernetn.gov)
No comments.

Engineering (Gary Lide - glide@lavernetn.gov)
No comments.

Utilities (Scott Tatalovich - statalovich@lavernetn.gov)
No comments.


Codes (Joe White - jwhite@lavernetn.gov)
No comments.

Fire (Curtis Brinkley - cbrinkley@lavernetn.gov)
No comments.

Police
No comments.

***Note:** The above technical items may not be the only corrections and/or issues needing to be resolved to get approval from the planning commission. New items can be brought up at the workshop and staff can add items at any time that might have been overlooked. It is the applicant's responsibility to make sure that all technical items are addressed and that no new issues exist before the planning commission meeting. Addressing all technical items does not constitute approval. It is the planning commission's decision whether an item passes

or fails. Revised plans are due to staff by the following Monday at close of business unless other arrangements are made and documented.



MAP 29, PARCEL 21.01
SUNTRUST, TRUSTEE
R.B. 1507, PG. 2285
ZONED R-4

MAP 29, PARCEL 20.00
JOHN M. BYRNES
D.B. 545, PG. 456
ZONED I-2


MAP 29, PARCEL 21.00
LMP, LLC
R.B. 1066, PG. 2478
ZONED R-4

MAP 32, PARCEL 9.00
NARON FAMILY TRUST
R.B. 52, PG. 398

MAP 32, PARCEL 9.00
NARON FAMILY TRUST
R.B. 52, PG. 398

MAP 32, PARCEL 6.04
SANDRA M. PARKER
R.B. 579, PG. 1539
ZONED R-1

MAP 32, PARCEL 8.00
LARRY J. GIBBONS
R.B. 573, PG. 2635
ZONED R-1



CERTIFICATE OF OWNERSHIP AND DEDICATION

I (WE) HEREBY CERTIFY THAT I AM (WE ARE) THE OWNER(S) OF THE PROPERTY SHOWN AND DESCRIBED HEREON AS EVIDENCED IN BOOK NUMBER 1655, PAGE 199, RUTHERFORD COUNTY REGISTERS OFFICE, AND THAT I (WE) HEREBY ADOPT THIS PLAN OF SUBDIVISION WITH MY (OUR) FREE CONSENT ESTABLISHING THE MINIMUM BUILDING RESTRICTION LINES AND THAT OFFERS OR IRREVOCABLE DEDICATION FOR ALL PUBLIC WAYS, UTILITIES, AND OTHER FACILITIES HAVE BEEN FILED.

DATE: 2-6-24 NAME: CRAN YERIAN, DIRECTOR OF LAND DEVELOPMENT
DEED REFERENCE: TAX MAP 29, PARCEL 20.04
TAX MAP 29N, GROUP "A", PARCEL 101
TAX MAP 29N, GROUP "A", PARCEL 151
RECORD BOOK 1655, PAGE 199

CERTIFICATE OF ACCURACY

I HEREBY CERTIFY THAT TO THE BEST OF MY KNOWLEDGE AND BELIEF THAT THIS IS A TRUE AND ACCURATE SURVEY OF THE PROPERTY SHOWN HEREON; THAT THIS SURVEY MEETS OR EXCEEDS THE MINIMUM REQUIREMENTS OF AN URBAN LAND SURVEY, CATEGORY "1", AS PER STANDARDS OF PRACTICE ADOPTED BY THE BOARD OF EXAMINERS FOR LAND SURVEYORS FOR THE STATE OF TENNESSEE, AND THAT THE RATIO OF PRECISION IS GREATER THAN 1:10,000.

DATE: 1/4/2024 NAME: Michael C. Roberts
REGISTERED LAND SURVEYOR
TENN. R.L.S. NO. 2064



CERTIFICATE OF APPROVAL OF WATER SYSTEM

I HEREBY CERTIFY THAT THE WATER SYSTEMS OUTLINED OR INDICATED ON THE FINAL SUBDIVISION PLAT ENTITLED "PORTICO PLACE SECTION 2, PHASE 2" HAS/HAVE BEEN INSTALLED IN ACCORDANCE WITH CURRENT LOCAL AND STATE GOVERNMENT REQUIREMENTS, OR A SUFFICIENT BOND OR OTHER SURETY HAS BEEN FILED TO GUARANTEE SAID INSTALLATION.

DATE: 08 FEB 2024 NAME: Gray
AUTHORIZED APPROVING AGENT

CERTIFICATE OF APPROVAL OF SEWER SYSTEM

I HEREBY CERTIFY THAT THE SEWER SYSTEMS OUTLINED OR INDICATED ON THE SUBDIVISION FINAL PLAT ENTITLED "PORTICO PLACE SECTION 2, PHASE 2" HAVE BEEN INSTALLED IN ACCORDANCE WITH CURRENT LOCAL AND STATE GOVERNMENT REQUIREMENTS, OR A SUFFICIENT BOND OR OTHER SURETY HAS BEEN FILED TO GUARANTEE SAID INSTALLATION.

DATE: 2-1-2024 NAME: Gray
AUTHORIZED APPROVING AGENT

CERTIFICATE OF APPROVAL OF PUBLIC WAYS FOR BOND POSTING

I HEREBY CERTIFY THAT ALL DESIGNATED PUBLIC WAYS ON THIS FINAL SUBDIVISION PLAT HAVE BEEN INSTALLED IN AN ACCEPTABLE MANNER AND ACCORDING TO THE SPECIFICATIONS OF THE LAVERGNE SUBDIVISION REGULATIONS, OR (IF) THAT A PERFORMANCE BOND OR OTHER SURETY HAS BEEN POSTED WITH THE PLANNING COMMISSION TO GUARANTEE COMPLETION OF ALL REQUIRED IMPROVEMENTS IN CASE OF DEFAULT.

DATE: 08 FEB 2024 NAME: Gray
AUTHORIZED APPROVING AGENT

CERTIFICATE OF APPROVAL FOR RECORDING

I HEREBY CERTIFY THAT THE SUBDIVISION PLAT SHOWN HEREON HAS BEEN FOUND TO COMPLY WITH THE LAVERGNE SUBDIVISION REGULATIONS, WITH THE EXCEPTION OF SUCH VARIANCES, IF ANY, AS ARE NOTED IN THE MINUTES OF THE PLANNING COMMISSION, AND THAT IT HAS BEEN APPROVED FOR RECORDING IN THE OFFICE OF THE COUNTY REGISTER.

DATE: 2/13/24 NAME: Gray
SECRETARY, PLANNING COMMISSION

FINAL PLAT - COVER SHEET

SECTION 2, PHASE 2 AND RESUBDIVISION OF COMMON AREAS A & B OF SECTION 2, PHASE 1 PORTICO PLACE SUBDIVISION

CITY OF LAVERGNE, TENNESSEE
3rd CIVIL DISTRICT, RUTHERFORD COUNTY

SEC, Inc. SITE ENGINEERING CONSULTANTS
ENGINEERING • SURVEYING • LAND PLANNING
850 MIDDLE TENNESSEE BLVD • MURFREESBORO, TENNESSEE 37129
PHONE (615) 890-7901 • FAX (615) 895-2567

PROJ. # 17024 DATE: 4-26-23 FILE: 17024 - PPS/CP2PHO DRAWN BY: ATG SCALE: 1" = 100' SHEET 48 of 49

GENERAL NOTES

- THE PURPOSE OF THIS FINAL PLAT IS TO CREATE 52 SINGLE FAMILY LOTS BEING SUPPORTED WITH ROAD RIGHT-OF-WAY AND EASEMENTS.
- BEARING SYSTEM IS BASED ON TENNESSEE STATE PLANE COORDINATES TIED TO RUTHERFORD COUNTY CONTROL POINT RCC-01 (NAD 83-96).
- THIS PROPERTY LIES WITHIN ZONE X, NOT IN A SPECIAL FLOOD HAZARD AREA, PER FEMA FIRM MAPS FOR RUTHERFORD COUNTY, MAP NO. 4749C0105 J, EFFECTIVE DATE: MAY 9, 2023.
- PARCELS MAY BE SUBJECT TO ADDITIONAL EASEMENTS AND/OR RESTRICTIONS, BY RECORD OR PRESCRIPTION, THAT A COMPLETE TITLE SEARCH MAY REVEAL.
- PROPERTY IS ZONED PDR. MINIMUM SETBACK REQUIREMENTS ARE:
FRONT - 15 FT. / (35 FT. TO GARAGE) - SIDE - 5 FT. - REAR - 15 FT.
- FOR EACH LOT SHOWN ON THIS PLAT, THERE SHALL BE PLANTED A MINIMUM OF ONE CANOPY TREE OF AT LEAST 2.5" CALIBER AND ONE UNDERSTORY TREE OF AT LEAST 1.5" CALIBER. THE TYPE OF TREE IS TO BE DETERMINED BY THE CITY OF LAVERGNE WITH THE DEVELOPER.
- ALL CRITICAL LOTS (WITH 15% SLOPES OR GREATER), ARE DENOTED WITH AN ASTERISK (*) ENGINEERED LOT PLANS ARE REQUIRED FOR THESE LOTS PRIOR TO OBTAINING A BUILDING PERMIT.
- ALL COMMON AREAS AND DRAINAGE AREAS SHALL BE OWNED AND MAINTAINED BY THE HOMEOWNERS ASSOCIATION.
- DEVELOPER IS RESPONSIBLE FOR THE INSTALLATION OF STREET LIGHTS. STREET LIGHTS SHALL BE LOCATED NO MORE THAN 300 FEET APART.
- LOTS 34-39 AND 43-53 SHALL HAVE NO ACCESS TO BLAIR ROAD. ALL ACCESS FOR THESE LOTS SHALL BE FROM AND TO CORNICE DRIVE FOR LOTS 34-39 AND PORTICO PLACE FOR LOTS 43-53.
- CONSTRUCTION OR MOVING OF SOILS IS NOT ALLOWED WITHIN THE STREAM BUFFERS. NO VARIANCE WILL BE GRANTED FOR LOT 34.

CURVE DATA

CURVE	DELTA	RADIUS	ARC LENGTH	CHORD BEARING	CHORD LENGTH
C1	6°45'43"	500.00'	59.01'	S 79°52'45" W	58.97'
C2	6°45'43"	500.00'	59.01'	S 86°38'31" W	58.97'
C3	6°45'43"	500.00'	59.01'	N 86°35'46" W	58.97'
C4	6°01'34"	500.00'	52.59'	N 60°12'07" W	52.56'
C5	6°01'34"	500.00'	52.59'	N 74°10'53" W	52.56'
C6	6°45'43"	500.00'	59.01'	N 67°46'55" W	58.97'
C7	6°01'34"	500.00'	52.59'	N 62°23'05" W	52.56'
C8	6°01'34"	500.00'	52.59'	N 55°24'42" W	52.56'
C9	2°00'09"	500.00'	17.47'	N 52°20'50" W	17.47'
C10	125°58'52"	175.00'	82.41'	N 36°02'00" W	81.63'
C11	3°36'01"	175.00'	98.52'	N 07°33'54" W	95.30'
C12	22°02'31"	175.00'	67.32'	N 19°15'22" E	66.91'
C13	30°00'00"	25.00'	39.27'	N 78°16'58" E	35.36'
C14	16°17'36"	220.00'	62.56'	S 67°52'01" E	62.35'
C15	6°26'38"	50.00'	5.62'	N 62°56'41" W	5.62'
C16	14°12'41"	445.37'	3.64'	N 78°17'29" E	3.64'
C17	47°39'58"	50.00'	4.60'	S 28°49'13" E	4.61'
C18	48°44'32"	50.00'	4.254'	S 77°02'27" E	4.26'
C19	50°00'00"	25.00'	39.27'	S 44°33'22" E	35.36'
C20	28°51'22"	50.00'	24.18'	N 64°10'55" E	24.36'
C21	70°31'44"	25.00'	30.77'	N 85°00'46" E	28.87'
C22	4°35'00"	225.00'	18.00'	S 7°45'05" W	18.00'
C23	10°15'58"	225.00'	40.05'	S 50°35'53" W	40.00'
C24	1°28'42"	225.00'	45.08'	S 09°45'14" W	45.00'
C25	10°15'58"	225.00'	40.05'	S 0°05'06" E	40.00'
C26	10°15'58"	225.00'	40.05'	S 1°17'04" E	40.00'
C27	1°28'42"	225.00'	45.08'	S 22°07'24" E	45.00'
C28	10°15'58"	225.00'	40.05'	S 32°47'44" E	40.00'
C29	10°15'58"	225.00'	40.05'	S 43°04'42" E	40.00'
C30	2°05'06"	225.00'	8.19'	S 49°18'13" E	8.19'
C31	3°20'03"	550.00'	32.00'	S 60°04'47" E	32.00'
C32	4°09'51"	550.00'	39.91'	S 54°45'54" E	39.91'
C33	5°11'13"	550.00'	49.79'	S 50°25'56" E	49.77'
C34	3°10'16"	550.00'	48.75'	S 63°37'09" E	49.77'
C35	4°09'51"	550.00'	39.91'	S 74°27'00" E	39.91'
C36	4°09'51"	550.00'	39.91'	S 74°27'00" E	39.91'
C37	4°39'58"	550.00'	44.75'	S 78°16'46" E	44.78'
C38	4°09'51"	550.00'	39.91'	S 82°26'00" E	39.91'
C39	4°09'51"	550.00'	39.91'	S 82°26'00" E	39.91'
C40	4°09'51"	550.00'	39.91'	N 88°24'27" E	39.91'
C41	4°09'51"	550.00'	39.91'	N 84°14'56" E	39.91'
C42	4°09'51"	550.00'	39.91'	N 80°05'25" E	39.91'
C43	3°32'00"	550.00'	33.92'	N 76°14'39" E	33.91'
C44	2°24'32"	170.00'	88.50'	N 74°58'17" E	87.50'
C45	13°32'02"	220.00'	61.91'	N 84°17'00" W	61.89'
C46	2°10'18"	500.00'	17.64'	S 78°29'18" E	17.64'
C47	18°49'14"	50.00'	10.63'	N 54°23'23" E	10.63'
C48	18°26'33"	448.37'	15.01'	N 68°17'30" E	15.01'
C49	18°56'33"	50.00'	13.91'	N 22°41'49" E	13.87'
C50	37°32'58"	30.00'	203.16'	N 48°26'34" E	199.55'
C51	0°44'16"	448.37'	5.74'	N 73°39'09" E	5.74'
C52	13°14'09"	459.84'	106.23'	N 82°20'37" E	105.99'

LOT AREA TABLE

LOT	AREA - SQ. FT.	ACRES
1	6,473.05	0.15
2	6,473.05	0.15
3	6,473.05	0.15
4	6,473.05	0.15
5	6,473.05	0.15
6	6,473.05	0.15
7	6,473.05	0.15
8	6,473.05	0.15
9	6,473.05	0.15
10	6,473.05	0.15
11	6,473.05	0.15
12	6,473.05	0.15
13	6,473.05	0.15
14	6,473.05	0.15
15	6,473.05	0.15
16	6,473.05	0.15
17	6,473.05	0.15
18	6,473.05	0.15
19	6,473.05	0.15
20	6,473.05	0.15
21	6,473.05	0.15
22	6,473.05	0.15
23	6,473.05	0.15
24	6,473.05	0.15
25	6,473.05	0.15
26	6,473.05	0.15
27	6,473.05	0.15
28	6,473.05	0.15
29	6,473.05	0.15
30	6,473.05	0.15
31	6,473.05	0.15
32	6,473.05	0.15
33	6,473.05	0.15
34	6,473.05	0.15
35	6,473.05	0.15
36	6,473.05	0.15
37	6,473.05	0.15
38	6,473.05	0.15
39	6,473.05	0.15
40	6,473.05	0.15
41	6,473.05	0.15
42	6,473.05	0.15
43	6,473.05	0.15
44	6,473.05	0.15
45	6,473.05	0.15
46	6,473.05	0.15
47	6,473.05	0.15
48	6,473.05	0.15
49	6,473.05	0.15
50	6,473.05	0.15
51	6,473.05	0.15
52	6,473.05	0.15

LINE TABLE


LINE	BEARING	DISTANCE
L1	S 08°06'55" W	16.38'
L2	S 0°48'24" W	57.41'
L3	S 06°55'57" E	67.80'
L4	S 83°04'03" W	26.00'
L5	S 06°55'57" E	50.00'
L6	N 89°04'03" E	32.56'
L7	S 06°55'57" E	76.01'
L8	S 20°14'48" E	55.73'
L9	S 29°02'23" E	49.61'
L10	S 29°24'42" E	47.89'
L11	S 21°53'31" E	41.99'
L12	S 08°39'21" E	24.86'
L13	S 76°40'26" W	32.68'
L14	S 83°10'15" W	21.44'
L15	N 59°43'22" W	30.34'
L16	S 59°02'05" W	28.31'
L17	N 12°34'44" W	24.91'
L18	S 85°00'48" W	26.12'
L19	N 50°16'36" E	34.39'

OPEN SPACE AREA TABLE

AREA	SQ. FEET	ACRES
OPEN SPACE A	54,042	1.24
OPEN SPACE B	132,609	3.04
OPEN SPACE C	7,437	0.16
OPEN SPACE D	32,537	0.75
OPEN SPACE E	53,963	1.24

RIGHT-OF-WAY AREA TABLE

AREA	SQ. FEET	ACRES
RIGHT-OF-WAY	64,541	1.34



TYPICAL MINIMUM BUILDING SETBACKS

OWNER/DEVELOPER:
BLAIR ROAD, LLC
CORPORATE OFFICE:
572 SAVANNAH HWY.
CHARLESTON, SC 29407
LOCAL OFFICE:
101 FORREST CROSSING, SUITE 107,
FRANKLIN, TN 37064

LAND DATA:
ZONING: PDR
52 LOTS ON 15.69± ACRES

BUILDING SETBACKS:
FRONT: 15'
SIDE: 5'
REAR: 15'

DEED REFERENCE:
TAX MAP 29, PARCEL 20.04
RECORD BOOK 1655, PAGE 199

REVISED COMMON AREA:
TAX MAP 29N, GROUP "A", PARCEL 101
&
TAX MAP 29N, GROUP "A", PARCEL 151

PORTICO PLACE
SECTION 2, PHASE 1
P.B.K. 46, PG. 212-214

PLAT BOOK 49, PAGE 286-287

TIME OF RECORDING: 12:09 P.M.

DATE OF RECORDING: February 14, 2024

Heather Dabbern, Register
Rutherford County Tennessee
Rec'd #: 1241623
Rec'd: 30.00 Instrument #: 2832272
State: 0.00
Clerk: 0.00
Other: 2.00 2/14/2024 at 12:09 PM
Total: 32.00
Plat Cabinet 49 Pgs 286-287

Re-grade swell, straw mat when complete

Remove any erosion control, straw mat areas that are in need. Most of this is vegetation, shouldn't need much straw mat

Remove any erosion control, straw mat areas that are in need. Most of this is vegetation, shouldn't need much straw mat

Backfill around mailboxes and seed and straw.

Remove any erosion control, straw mat areas that are in need. Most of this is vegetation, shouldn't need much straw mat

CURVE	DEL	RADIUS	ARC LENGTH	CRD BEARING	CRD LENGTH
C1	6°45'43"	500.00'	29.01'	S 74°24'39" W	58.97'
C2	6°45'43"	500.00'	59.01'	S 86°38'31" W	58.97'
C3	6°45'43"	500.00'	59.01'	N 86°38'31" W	58.97'
C4	6°45'43"	500.00'	59.01'	N 80°02'07" W	58.97'
C5	6°45'43"	500.00'	59.01'	N 74°10'53" W	58.97'
C6	6°45'43"	500.00'	59.01'	N 67°46'55" W	58.97'
C7	6°45'43"	500.00'	59.01'	N 55°21'42" W	58.97'
C8	6°45'43"	500.00'	59.01'	N 42°00'00" W	58.97'
C9	6°45'43"	500.00'	59.01'	N 28°49'13" W	58.97'
C10	6°45'43"	500.00'	59.01'	N 15°15'22" E	58.97'
C11	6°45'43"	500.00'	59.01'	N 01°43'52" E	58.97'
C12	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C13	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C14	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C15	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C16	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C17	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C18	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C19	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C20	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C21	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C22	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C23	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C24	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C25	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C26	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C27	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C28	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C29	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C30	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C31	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C32	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C33	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C34	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C35	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C36	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C37	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C38	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C39	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C40	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C41	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C42	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C43	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C44	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C45	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C46	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C47	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C48	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C49	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'
C50	6°45'43"	500.00'	59.01'	N 00°00'00" E	58.97'

LOT AREA TABLE
AREA SQ. FT. ACRES
1 6,473.05 0.15
2 6,473.05 0.15
3 6,473.05 0.15
4 6,473.05 0.15
5 6,473.05 0.15
6 6,473.05 0.15
7 6,473.05 0.15
8 6,473.05 0.15
9 6,473.05 0.15
10 6,473.05 0.15
11 6,473.05 0.15
12 6,473.05 0.15
13 6,473.05 0.15
14 6,473.05 0.15
15 6,473.05 0.15
16 6,473.05 0.15
17 6,473.05 0.15
18 6,473.05 0.15
19 6,473.05 0.15
20 6,473.05 0.15
21 6,473.05 0.15
22 6,473.05 0.15
23 6,473.05 0.15
24 6,473.05 0.15
25 6,473.05 0.15
26 6,473.05 0.15
27 6,473.05 0.15
28 6,473.05 0.15
29 6,473.05 0.15
30 6,473.05 0.15
31 6,473.05 0.15
32 6,473.05 0.15
33 6,473.05 0.15
34 6,473.05 0.15
35 6,473.05 0.15
36 6,473.05 0.15
37 6,473.05 0.15
38 6,473.05 0.15
39 6,473.05 0.15
40 6,473.05 0.15
41 6,473.05 0.15
42 6,473.05 0.15
43 6,473.05 0.15
44 6,473.05 0.15
45 6,473.05 0.15
46 6,473.05 0.15
47 6,473.05 0.15
48 6,473.05 0.15
49 6,473.05 0.15
50 6,473.05 0.15
51 6,473.05 0.15
52 6,473.05 0.15
53 6,473.05 0.15
54 6,473.05 0.15
55 6,473.05 0.15
56 6,473.05 0.15
57 6,473.05 0.15
58 6,473.05 0.15
59 6,473.05 0.15
60 6,473.05 0.15
61 6,473.05 0.15
62 6,473.05 0.15
63 6,473.05 0.15
64 6,473.05 0.15
65 6,473.05 0.15
66 6,473.05 0.15
67 6,473.05 0.15

LINE TABLE		
LINE	BEARING	DISTANCE
L1	S 06°06'55" W	16.38
L2	S 0°49'24" W	57.41
L3	S 06°55'57" E	67.80
L4	S 63°04'03" W	26.00
L5	S 06°55'57" E	50.00
L6	N 63°04'03" E	32.51
L7	S 06°55'57" E	76.07
L8	S 20°14'48" E	55.73
L9	S 25°02'27" E	49.67
L10	S 29°24'44" E	47.89
L11	S 29°59'31" E	41.99
L12	S 19°32'21" E	24.86
L13	S 78°40'26" W	32.68
L14	S 83°48'05" W	21.44
L15	N 59°43'52" W	30.34
L16	S 19°59'02" W	28.31
L17	N 1°23'44" W	24.97
L18	S 85°00'46" W	26.82
L19	N 30°16'58" E	34.39

OPEN SPACE AREA TABLE		
EN SPACE	AREA	AREA
EN SPACE A	54,042	124
EN SPACE B	132,609	3.04
EN SPACE F	7,157	0.16
EN SPACE G	32,537	0.75
EN SPACE H	53,963	1.24

RIGHT-OF-WAY AREA TABLE

AREA	SQ. FEET	ACRES
RIGHT-OF-WAY	84,541	1.94

Heather Dabern, Registrar Rutherford County Tennessee	Instrument #: 2532272
Rec'd: 30.00	Recorded: 2/14/2024 at 12:09 PM
State: 0.00	Other: in
Clerk: 2.00	Total: 32.00
Plat Cabinet: 49 Pgs: 286-297	

OWNER/DEVELOPER:
BLAIR ROAD, LLC
CORPORATE OFFICE:
572 SAVANNAH HWY.
CHARLESTON, SC 29407
LOCAL OFFICE:
101 FORREST CROSSING, SUITE 107,
FRANKLIN, TN 37064

LAND DATA:
ZONING: PDR
52 LOTS ON 15.69± ACRES

BUILDING SETBACKS:
FRONT: 15'
SIDE: 5'
REAR: 15'

DEED REFERENCE:

TAX MAP 29, PARCEL 20.04
RECORD BOOK 1655, PAGE 119

REVISED COMMON AREA:
TAX MAP 29N, GROUP "A", PARCEL 1.01
TAX MAP 29N, GROUP "A", PARCEL 15.01

PLAT BOOK 49, PAGE 286-287
TIME OF RECORDING: 12:09 P.M.
DATE OF RECORDING: February 14, 2024

FINAL PLAT

SECTION 2, PHASE 2 AND RESUBDIVISION OF
COMMON AREAS A & B OF SECTION 2, PHASE 1
PORTICO PLACE SUBDIVISION

CITY OF LAVERGNE, TENNESSEE
3rd CIVIL DISTRICT, RUTHERFORD COUNTY

SEC, Inc. SITE ENGINEERING CONSULTANTS

ENGINEERING • SURVEYING • LAND PLANNING

850 MIDDLE TENNESSEE BLVD. • MURFREESBORO, TENNESSEE 37129

PHONE (615) 890-7901 • FAX (615) 895-2567

PROJ. #	DATE: 4-26-23	FILE:	DRAWN BY:	SCALE:	SHEET
17024	REV: 12-18-23	17024 - PPS2C2PH FINALPLAT	ATS	1" = 50'	2 OF 2